

SCIENTIFIC AMERICAN


[Entered at the Post Office of New York, N. Y., as Second Class matter. Copyrighted, 1892, by Munn & Co.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LXVII.—No. 16,
ESTABLISHED 1845

NEW YORK, OCTOBER 15, 1892.

\$3.00 A YEAR.
WEEKLY.



THE NEW SANTA MARIA, REPLICA OF COLUMBUS' VESSEL, WHICH IS TO BE SAILED ACROSS THE ATLANTIC.—[See page 245.]

Scientific American.

ESTABLISHED 1845.

MUNN & CO., Editors and Proprietors

PUBLISHED WEEKLY AT

No. 361 BROADWAY, NEW YORK.

O. D. MUNN.

A. E. BEACH.

TERMS FOR THE SCIENTIFIC AMERICAN.

One copy, one year, for the U. S., Canada or Mexico. \$3 00
 One copy, six months, for the U. S., Canada or Mexico. 1 50
 One copy, one year, to any foreign country belonging to Postal Union. 4 00
 Remit by postal or express money order, or by bank draft or check.
 MUNN & CO., 361 Broadway, corner of Franklin Street, New York.

The Scientific American Supplement

is a distinct paper from the SCIENTIFIC AMERICAN. THE SUPPLEMENT is issued weekly. Every number contains 16 octavo pages, uniform in size with SCIENTIFIC AMERICAN. Terms of subscription for SUPPLEMENT, \$5.00 a year, for the U. S., Canada or Mexico, \$6.00 a year to foreign countries belonging to the Postal Union. Single copies, 10 cents. Sold by all newsdealers throughout the country. See prospectus, last page.

Combined Rates.—The SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for one year, to any address in U. S., Canada or Mexico, on receipt of seven dollars. To foreign countries within Postal Union, nine dollars a year.

Building Edition.

THE ARCHITECTS AND BUILDERS EDITION OF THE SCIENTIFIC AMERICAN is a large and splendid illustrated periodical, issued monthly, containing floor plans, perspective views, and sheets of constructive details, pertaining to modern architecture. Each number is illustrated with beautiful plates, showing desirable dwellings, public buildings and architectural work in great variety. To builders and all who contemplate building this work is invaluable. Has the largest circulation of any architectural publication in the world.

Single copies 25 cents. By mail, to any part of the United States, Canada or Mexico, \$2.50 a year. To foreign Postal Union countries, \$3.00 a year. Combined rate for BUILDING EDITION with SCIENTIFIC AMERICAN, \$5.00 a year; combined rate for BUILDING EDITION, SCIENTIFIC AMERICAN and SUPPLEMENT, \$9.00 a year. To foreign countries, \$11.50 a year.

Spanish Edition of the Scientific American.

LA AMERICA CIENTIFICA E INDUSTRIAL (Spanish trade edition of the SCIENTIFIC AMERICAN) is published monthly, uniform in size and typography with the SCIENTIFIC AMERICAN. Every number of *La America* is profusely illustrated. It is the finest scientific, industrial trade paper printed in the Spanish language. It circulates throughout Cuba, the West Indies, Mexico Central and South America, Spain and Spanish possessions—wherever the Spanish language is spoken. \$3.00 a year, post paid to any part of the world. Single copies 25 cents. See prospectus.

MUNN & CO., Publishers,
361 Broadway, New York.

✂ The safest way to remit is by postal order, express money order, draft or bank check. Make all remittances payable to order of MUNN & CO.

✂ Readers are specially requested to notify the publishers in case of any failure, delay, or irregularity in receipt of papers.

NEW YORK, SATURDAY, OCTOBER 15, 1892.

Contents.

(Illustrated articles are marked with an asterisk.)

Agricultural improvements, recent.	250	Meteor story, a false.	248
Battery, storage, monopoly.	242	Mineralogy, Dana's system of.	241
Battery, storage, the Logan.	244	Molecular motion.	248
Beton blocks, making and lifting.	243	Niagara Falls, water power*.	247
Canal, Chicago's new drainage.	249	Oil, mineral, Scotland.	241
Clay, fibrous.	244	Oxyphenine.	240
Colors in dyeing cotton goods.	249	Patents granted, weekly record.	251
Columbian celebration.	240	Printing of woolen tissues.	242
Columbus' ship Santa Maria*.	238	Railway inventions, recent.	250
Columbus, the best picture of.	246	Rocking chair, fan*.	242
Cotton prints, arsenic in.	249	Rubbers.	242
Disinfection by means of sulphur.	242	Salesman, the electrical.	243
Edison's patents sustained.	245	Santa Maria, the*.	239
Fabrics, piled, ornamental.	247	Saw mill, MacRey's gang*.	242
Fan for rocking chairs*.	242	Search light, the Mount Washington.	248
Foundations, curious.	247	Steam on the highway.	245
Horn, a musical.	249	Sugar factories, German.	245
Inventions recently patented.	249	Toy bugle*.	249
Locomotives, horse power of.	241	Tungsten, metallic.	249
Loes, big, for the World's Fair.	246	Valve, a four-foot water*.	246
Mechanical appliances, some new.	250	Watches, how to demagnetize (4559).	251
		World's Fair items.	245

TABLE OF CONTENTS OF

SCIENTIFIC AMERICAN SUPPLEMENT

No. 876.

For the Week Ending October 15, 1892.

Price 10 cents. For sale by all newsdealers

I. ASTRONOMY.—The Opposition of Mars.—Prof. Pickering's observations in Peru during the opposition of the planet Mars.—3 illustrations.	14002
II. BIOGRAPHY.—Christopher Columbus.—A graphic account of Columbus' life and works.—Scenes in his life.—Present and proposed memorials.—3 illustrations.	13991
Hubert Howe Bancroft.—The life of the historian, and the story of his unprecedented life's work in the compilation of his history.—1 illustration.	13992
III. CHEMISTRY.—A Filter for "Mayer" Estimations.—By F. C. J. BIRD.—Apparatus for alkaloidal titrations.—1 illustration.	14005
New Form of Carbon.—A most interesting addition to the chemistry of carbon.—Graphitite, a new form of carbon.	14006
Tests for Vegetable Waxes.—Tests to distinguish ten vegetable waxes from each other.	14006
IV. EDUCATION.—The Progress Made in Teaching Deaf Children to Read Lips and Talk in the United States and Canada.—By ALEXANDER GRAHAM BELL.—A plea for the new system of speaking, with valuable statistics.	13994
V. FINE ART.—Burns Memorial Statue, Ayr.—Recently erected statue of the Scotch poet.—1 illustration.	13994
VI. GEOLOGY.—How Old is the World? By the Rev. H. N. HUTCHINSON, B.A., F.G.S.—What geology tells us of the story of the earth; the probability of its age.	13996
VII. HORTICULTURE.—A Floral Clock.—A horizontal clock, with figures in plants, and flower-covered hands; details of the mechanism.—2 illustrations.	13998
The Daisy Pea.—A new pea of excellent quality and dwarf growth.—1 illustration.	13998
VIII. HYGIENE.—How to Purify Drinking Water.—By Prof. PETER T. AUSTEN, Ph.D., F.C.S.—A most valuable contribution to the chemistry of sanitation; how to use alum in purifying water.	14000
Subcutaneous Injections of Testicular Fluid.—Further communication from Dr. Brown-Sequard, referring to his elixir of life.	14001
IX. MISCELLANEOUS.—Compressed Food.—Food adapted for travelers and explorers, as well as for army use; a recent industry.	14001
The Accident at Bezers.—A peculiar and fatal accident upon a railroad bridge, due to derailment of the engine.—1 illustration.	13995
X. NAVIGATION.—Icebergs.—All about icebergs at sea: their dangers, how they are encountered, and their various appearances.	13995
XI. PHYSICS.—Luminosity of Hydrocarbon Flames.—By VIVIAN B. LEWES, Royal Naval College, Greenwich.—A contribution to the technology of artificial illumination, with formulae and tables.	14004
XII. PHYSIOLOGY.—Death.—By P. CHALMERS MITCHELL.—A scientific view of life and death; what death is from the standpoint of physiological science.	13999
XIII. TECHNOLOGY.—Essence of Lemon.—By ARTHUR A. BARRETT, Messina.—How this essence is made, and its adulterations and impurities.	14006
The Production of Heating Gas and Ammonia.—By A. HENNING, M.A.I.M.E.—A modification of the gas-producing process, for the increase of the yield of ammonia.	14005

THE COLUMBIAN CELEBRATION OF OCTOBER, 1892.

When this paper reaches our readers, New York will have been the scene of one of the most impressive spectacles it has ever been her fortune to witness. The four hundredth anniversary of the discovery of America by Columbus will have been signalized by parades on land and water, by exhibitions, by decorations of buildings, by meetings of societies and by all the means employed to commemorate great deeds. In a practical age and in the midst of a practical nation, one distinctively of modern times, it is a good sign to see the entire populace alive to the great deeds of preceding centuries. What America lacks is full association with the past. Compared with the European countries, she seems but a modern creation. But in this commemoration of Columbus' work, America asserts her rights in the past, lays claim to an inheritance in the story of the ages which is more valuable than much that Europe can claim.

The story is so picturesque; the departure of the three ships on the ocean, ships which to-day would be deemed unseaworthy, bound, like Hiawatha, "westward, westward;" the weary voyage, the dissensions of the mariners, the encouragement derived from the sea drift which was encountered, the landing at the end of the three months' voyage, is an epitome of all that is best and most courageous in man. In those three months the destiny of a great continent was disposed of, and the history of the world was modified.

America, in the last four centuries, has led the world in many things. In material progress, the increasing rapidity of her development has been without parallel. In old times the civilization of a country was a slow process. The requisite increase of population, the replacing of savage or semi-savage customs by more advanced ones, was a work of time. But here the work, slow at the beginning, has gone on with accelerated speed. Three centuries nearly lapsed before the scattered settlers of the colonies defied and conquered the most powerful nation of Europe. The country for half a century more was lighted at night with candles and whale oil; its mails were transported by stage and horse; its roads were almost impassable in winter; its methods were still of the past.

Within the lifetime of many the new era began. A few experimental railroads, to be operated by horse power, were built. An engine was tried on one of them. The seed germinated, and within a generation the great area is covered with a network of railroads.

Next some scientists begin experimenting with electricity. The entire subject excites but little interest. When Congress is asked for an appropriation, it is but grudgingly granted. The message, "What hath God wrought?" goes down the wire, and, after a few years, the railroads are paralleled with telegraph lines.

There was no question of replacing old established stage or diligence lines with railroads. The carrying of the mails over districts a few hundred miles in extent was not the issue. An area large enough to constitute a continent was to be the scene. The lines were to go through wildernesses and over deserts. The lives of the builders were to be sacrificed to the savage aborigines before the great work could be done. And with all the difficulties the older countries may be fairly allowed to be defeated in the race. Columbus' achievement in its enterprise and daring and in its success was a pledge of the work which has since been done in the land he sailed to.

Looking over the busy scene of enterprise, there are feelings of regret to be mingled with admiration. The civilization of America means the extermination of entire races of mankind. The Northern Indians, human beings, who might have been a most important factor in their own land, have succumbed, and have almost disappeared. Their condition was well within the limits of the savage, yet they were intellectual, and were susceptible of training. The Christian missionaries to Great Britain were moved to effort, it is said, by the sight of British slaves on sale in the markets of Rome. To-day the same race has left its imprint on the entire face of the world, and shows the greatest powers of persistence of almost any people. It would seem that something might have been done with the thousands of Indians whose doom was sealed when Columbus set sail from Spain.

In the south most interesting civilizations have disappeared. Yucatan yields to the explorer ruins that indicate civilization probably as advanced as that of Egypt. The Incas of Peru seem to have been on the same high level. Yet all has disappeared, and Columbus led the way for the Caucasian army, which now holds sway over the entire hemisphere.

The celebration in this city is but a part of a year of celebration, which began last August in Spain and will end at Chicago in the Columbian Exposition. Not the least of the good effects will be the study of the life and times of the great discoverer, and the placing of his character upon a firm and authentic historical basis.

Elsewhere we describe some of the features of the work of the ensuing year and of the reproduction of the ships and of their old-time voyage. The future

may see more imposing celebrations, but another century must elapse to give an equally important era.

The Mineral Oil Industry of Scotland.

At a recent meeting of the Federated Institution of Mining Engineers, at Shelton, a paper by Mr. Robert Thomas Moore, on "The Mineral Oil Industry of Scotland," gave a brief notice of the progress and present position of the industry of shale distilling. It included descriptions of the geological and stratigraphical positions of the various seams of shale worked, including the now exhausted Boghead mineral, which yielded 2,337,932 tons in 1891, almost entirely from strata in the lower carboniferous or calciferous sandstone series; the methods of working, the machinery for breaking, and the distilling apparatus for crude oil; the subsequent refining operations being omitted, as being mainly chemical processes. The position of this branch of manufacture, in spite of the constant improvements in the yield from the material by the introduction of more exact methods of working, is, unfortunately, very unsatisfactory from the commercial point of view. Originally burning oil, which was the sole product, sold at 3s. per gallon, and the trade was a very profitable one; but, principally from the competition of natural American and Russian oils, the price has fallen to less than 6d. per gallon; and, although the yield has been supplemented by other products, such as paraffin wax and sulphate of ammonia, the business is not profitable, the price of the raw material and coal having so risen by the increase of 40 to 50 per cent in miners' wages that only a few of the companies have been able to avoid loss in working. The contrast between the original and the present condition of the trade will be seen in the following figures, giving the yield of products per ton of shale treated at the same works. In 1877 they were 30'499 gallons of crude oil and 17'37 pounds of sulphate of ammonia, together worth £1 3s. 2d.; while in 1891, 25'1 gallons of crude oil, 1'73 gallons of naphtha, and 27'23 pounds of sulphate of ammonia only realized 13s. 2d.; the price of the latter having declined from £17 5s. 6d. to £10 7s. 1d. per ton.

Oxyphenine.

This dyestuff makes its appearance in the form of a light yellowish brown powder, which is slightly soluble in cold, but more easily in hot water, to a dirty yellow solution. Alcohol produces a brownish yellow solution; sulphuric acid dissolves it, forming a brownish scarlet solution, which, on diluting with water, turns lemon yellow; hydrochloric acid and caustic soda throw down from aqueous solutions dirty reddish yellow precipitates. Oxyphenine is a direct color dyeing unmordanted cotton from a boiling bath containing soap and salt, going on evenly and easily, 3 per cent giving a deep golden yellow shade, while 1 per cent dyes a fine canary yellow. One merit of the dyestuff is that the dye bath is nearly exhausted, whereas with other yellows of this group much of the coloring matter remains in the bath.

On silk oxyphenine dyes from either a salt or acid bath, giving shades the same as those on cotton; half silk may be dyed in a simple salt bath. Wool may be dyed from either a salt or weak acid bath, but the shades have a more olive tone than those obtained on either cotton or silk. The color is turned a shade redder by strong acids; strong caustic soda has very little action, turning the tint a shade redder, but weak solutions have no action. Soaping has not the slightest action on the color, whether on cotton or wool, so that oxyphenine may be used on goods which have to be milled. Light appears to have little action. Swatches which have been exposed to the sun and air for three weeks show no sign of fading. Oxyphenine may, therefore, be classed among the fastest yellow dyestuffs at the disposal of the dyer. Oxyphenine may be used in calico printing, giving good yellows when printed on with the aid of soda crystals and a starch-gum thickening. A better plan still is to print on a color containing acetate of alumina, acetic acid, and a starch-gum thickening, the color being faster to soaping by this method than with the last. It may be also applied by padding.—*Dyer and Calico Printer.*

THE new twin-screw steamboat Richard Peck, built by the Harlan & Hollingsworth Company, at Wilmington, Del., for the New Haven steamboat line, made 20¼ miles an hour on her trial trip recently. The boat is 316 feet long over all, 48 feet beam over guards, and has a depth of hold of 18½ feet. Her horse power is 4,000 and her gross tonnage is 2,906. She was designed by A. Cary Smith.

UNINFLAMMABLE PETROLEUM.—Numerous processes have figured of late in the patent list whereby it is claimed that petroleum could be rendered inexplosive and also unflammable. One of these consists in adding to about forty gallons of petroleum two pounds of copper sulphate and stirring the whole well. After about six hours standing the oil is ready for use.

Sixth Edition of Dana's "System of Mineralogy."

The appearance of the successive editions of Prof. Dana's "System of Mineralogy" has been coincident with phases of mineralogical progress, which has made each of them not only symptomatic of a scientific era, but its reflection as well. They have, therefore, illustrated the changing conceptions of the mineralogical mind as a whole, and this cosmopolitan and liberal and practical tone recommended them to the high position they have attained as the *ex cathedra* utterances of the mineralogical faculty. In their *technique*, so to speak, they have shown the most practical and skillful arrangement of details, and their erudition has been equally remarkable and helpful. But they have also assumed the more important function of contributing original views as to the fundamental construction of the science, and this has resulted in a certain grandeur in their breadth of composition and an unmistakable forcefulness and completeness in their assertions. In the words of an English critic, "It is not too much to say that the publication of each successive edition of this work has constituted an epoch in the history of mineralogical science." When we turn back to the edition of the "System" in 1837, and open in succession the subsequent issues, we encounter one of the interesting phases through which all branches of science have passed and which persists in a diminishing degree to-day, viz., the elaboration of its nomenclature. Too much weight cannot be given to a system of nomenclature by which the designations of the separate species are firmly determined, and the terms of their description defined; but the scope and significance of nomenclature is given a deeper importance if we extend its meaning to the classification of species, their grouping, ordinal and family arrangement. Such a problem confronted mineralogists in 1830, and, somewhat dazzled by the unexpected and euphonious results flowing from the binomial system and the groupings of genera, families, orders and classes in botany and zoology, and anxious to confer upon this science the benefits of a device which seemed the apposite reflection in language of the measures and delimitations of nature, they undertook, under the leadership of Mohs, to arrange the mineral species according to a mingled consideration of their physical and chemical composition, and with this system Dana, in 1838, combined a peculiar and original scheme of binomial titles.

Few perhaps of the younger mineralogists and none of its latest students may be familiar with this very bold and independent effort, and the occasion of the appearance of the sixth edition of this great work seems an appropriate time to recall some of its details. It has an indelible interest as associated with the history of the science, and a still greater intellectual interest from the fact that Prof. Dana has gradually eliminated it as a whole, while preserving not only traces but representative parts of its more lucid and scientific features, features always co-ordinated with the chemical properties of minerals.

Prof. Dana, in introducing this "New Mineralogical Nomenclature" before the scientific world, said in his paper before the Lyceum of New York, in March, 1836, alluding to the system of Mohs, which he accepted: "In this arrangement M. Mohs has not wholly relied upon chemical characters, the exclusive adoption of which would have degraded mineralogy from the rank of an independent science, and merged it in that of chemistry; nor has he depended on physical characters solely; for although the latter are more especially employed, the author has throughout been guided to a certain extent by that important source of physical characters, viz., chemical composition. A cabinet arranged according to the system of Mohs presents, with remarkable clearness, a chain of affinities running through the whole, and connecting all the several parts. The *gases* and *liquids*, with which the arrangement commences, are followed by the *salts*, so disposed as to present an increase in stability, hardness, and luster, as the eye proceeds onward. Among the *gems*, we arrive at the diamond, in which these characters reach their climax. Then, descending in the series, we gradually pass through the *metallic oxides* to the *native metals*. In these the light-colored species are followed by the *sulphurets* and *arsenides* of similar color and luster, which are succeeded by the dark-colored metallic sulphurets; and these pass insensibly to the sulphurets without a true metallic luster. From the latter there is a natural transition to *sulphur*, and its close allies the *resins* and *coals*, with which the series terminates."

The minerals or mineralogical elements were grouped under the *Epigæa*, which included the fluids and all soluble minerals whose formation is now going on, the *Entogæa*, embracing those which occur in rock strata, and the *Hypogæa*, or those so deeply embedded in the earth's crust as to justify the appellation of buried. It was in the *Entogæa* that the larger number of the mineral species were placed. The *Epigæa* embraced gases, water, and soluble salts, as borax, alum, common salt, the alkaline salts, and the soluble secondary metallic salts, as copperas, blue and white vitriol, while the *Hypogæa* received the coals, bitumens, oils, etc. These

classes were again subdivided into orders, and these again into genera, and each mineral species received a binomial name under its appropriate genus.

A few examples of orders and genera from all these classes will illustrate the system without entering more minutely into details of the method.

In *Epigæa*, or the mineral substances found upon the earth, we find two orders, the *Rheutinea*, or fluids, including two genera, *Aer* and *Aqua*, and the *Sterinea*, or solids, containing the genera *Acidum*, *Borax*, *Alumen*, *Natron*, *Sal*, *Picralum*, *Nitrum*, *Vitriolum*, and *Gælum*. These genera were separated by considerations based upon chemical composition and upon hardness, gravity, and especially taste, as *weak sweetish alkaline*, *styptic*, *alkaline*, *purely saline*, *saline and bitter*, *cooling and saline*, *astringent and metallic*. The binomial scheme was applied in the following manner:

GENUS PICRALUM.

H.—15—25. G. 14—28. Taste saline and bitter.

P. glauveri.....	Glauber's salt.
P. thenardianum.....	Thenardite.
P. rhombicum.....	Epsom salt.
P. reussii.....	Reussite.
P. volcanicum.....	Mascagnine.
P. vesuvianum.....	Aphthalite.
P. octahedrum.....	Sal ammoniac.
P. deliquesens.....	Nitrate of magnesia.
P. tenellum.....	" " lime.

To the *Entogæa* were assigned, separated by hardness, gravity, luster, and streak, some eighty-two genera, and in looking for their determinative elements we find that they may comprehensively be grouped under chemical composition, chemical properties, as fusibility; physical features, as color, cleavage, luster; crystalline form or condition, as crystallized, massive, lamellar, etc.; geological accidents, as place of occurrence, volcanic, etc.; and associations, as granitic, etc. This system not only brought many mineral species into groups whose affinity is unquestioned to-day, and which are retained together, and must be upon any scientific basis of classification, but it also gathered into one genera very discordant neighbors and forced upon essentially distinct minerals a purely arbitrary and fictitious relationship.

Thus, under the order *Hyalinea*, so called from the high glassy luster possessed by its representatives, we find the genus *Hyalus* divided as follows:

H. bicolor.....	Iolite.
H. acutus.....	Axinite.
H. rhombohedrus.....	Quartz.
H. opalinus.....	Opal.
H. vulcani.....	Obsidian.
H. sphaerulus.....	Sphaerulite.
H. feriferus.....	Isopyre.

There was thus produced here a mixture of oxides, sub and uni silicates at the dictation of an extraneous fact, viz., luster; which, however correlated to density or molecular state, failed to express the esoteric principle which, in the philosophy of nature, establishes a truly natural classification in minerals. That esoteric principle was chemical *make-up*, which to-day rules the science and has shed such an abundant light over its dark places as to enlist it among the most finished and most rational sciences of our age. Chemical composition has been found to be the co-ordinating principle which enters most profoundly into all the varied aspects of minerals and binds into certain necessary sequences crystalline form, hardness, luster, and optical characters.

The third class of Dana under this system was the *Hypogæa*, or those so-called buried minerals. In this there were two orders, *Pittinea* and *Anthracinea*. Under the first were gums, bitumens, resins, and under the latter coal and graphite. The recent large extension of the hydrocarbons could not have enjoyed its present comparatively intelligent arrangement if a system of color, translucency, etc., as here adopted, had been retained. Among these organic products, as among the inorganic species, chemistry was alone able to disperse the confusion of discrepant groupings and give to the mineralogist the guidance of her dictum as to their genealogy and kinship.

The affinities of chemical composition was the Ariadne thread which led the mineralogist through the Dædalian labyrinth of mineral species, or perhaps, less strainedly, it was the standard of reference by which they were given their natural positions. To the chemical law Prof. Dana has more and more closely adhered, while he has in this last work advanced along the line of chemical chronology and inspected, in the difficult compounds formerly classed as margarophyllites and in the micas, under the suggestions of Tschermak and Clarke, the perplexing questions of their generation from some fundamental hypothetical molecule.

This chemical plan has separated the aggregate of mineral species into native elements, arsenides, sulphides, antimonides, sulph-arsenides, sulph-antimonides, and other alkaloidal unions, into the oxides, hydrous and anhydrous, the silicates, uni, bi and sub, with later modifications introduced in this sixth edition, the hydrous silicates and the oxygen salts, as carbonates, tantalates, columbates, sulphates, etc., a system practically maintained to-day, with changes

more or less material in their succession and interpretation.

In the fifth edition, based upon this plan of chemical reference, Prof. Dana attacked the momentous question of synonymy, and forced upon the science a unifying device of substantive terminations, the classic if not somewhat monotonous *ite*. The review of this section of the subject by Prof. Dana in the fifth edition was very explicit and frank.

When we compare the last, sixth, edition with its immediate predecessor, we find that the science has greatly enlarged its material scope and has also changed some of its points of view. With the growth in the number of species there have been attendant consolidations of species and reference of former species to varieties. There is also shown the evidence of new light or at any rate new conceptions in the treatment of the silicates, and, to a large degree, the groupings have been rearranged, while the succession or sequence of groups and divisions has been extensively altered. The fundamental plan of the fifth edition has been adhered to, and it would be difficult to devise a method and typographical treatment more expressive and convenient.

In the place of the bi, mono and sub silicates with the hydrous silicates, more or less hypothetically separated under these three sections, we have the di, poly, meta, ortho and sub silicates. The disilicates are salts of disilicic acid, $H_2Si_2O_5$, and have an oxygen ratio of silicon to bases of 4:1, and are represented by *petalite*; the polysilicates are salts of polysilicic acid, $H_2Si_3O_8$, and have an oxygen ratio of 3:1, and are represented by the feldspars; the metasilicates are salts of metasilicic acid, H_2SiO_3 , and have an oxygen ratio of 2:1, and are represented by *pyroxene* and *amphibole*; the orthosilicates are salts of orthosilicic acid, H_4SiO_4 , having an oxygen ratio of 1:1, of which the garnets are representative; and, lastly, the sub-silicates, in which the oxygen of the bases exceeds that of the silicic acid. The system has many exceptions, and seems hardly to introduce any chemical conceptions or aid in the realization of the facts of nature more clearly than the old method, which regarded the excess of silica (as would be the case in the di and poly silicates of this system) as unsaturated acid of the ordinary type.

The species *titanite*, *keilhanite*, *guarivite*, *astrophyllite* and *perofskite* are considered titano-silicates, and are placed at the end of the silicates, between which and the niobates, tantalates, etc., they form an interconnecting link or at least are regarded as doing so. The carbonates precede the silicates, and quartz, which formerly ended the oxides, now, by a natural precedence, leads the list. A few substituted names or combined species for older ones strike the eye. Naselite replaces nasite, raimondite covers apatelite, lazurite replaces lapis lazuli, pinite is added to muscovite, tennantite is combined with tetrahedrite, salite takes the place of salinite, bastite or Schiller spar is put under hypersthene, iadeite receives a much fuller treatment, klipsteinite is put under rhodonite, kupfferite under anthophyllite, giesekite under nephelite, as a long-supposed alteration product of that species. The investigation of Klein into the double refraction of garnets is incorporated, and the optical anomalies of other species, as explained by this author, also noted. Humite is separated from chondrodite, with a new species, clinohumite (1876). These three species are discussed together. Phlogopite is appended to biotite and also lepidomelane. The treatment of columbite is much expanded. Gummite and uraninite are placed under the uranates. The so-called perofskite of Magnet Cone, Arkansas, is made a titano-niobate of calcium and iron and placed under the name dyslanotite.

The crystallographic part of the system has been extensively revised. Nearly all of the 1,400 figures are either newly drawn or are new drawings of old figures, the angles of fundamental forms have been traced to the original authorities, and from them the axes have been determined by calculation, and the angles recalculated of the more important and common forms. The numerous interpolations of new species has displaced the old species from their numeral position, as well as their rearrangement. The vast amount of mineralogical investigation which has accumulated in recent years has been examined, and its substantial and permanent results given.

The sixth edition of Dana's "System of Mineralogy" places the science of minerals in a unique position, for it furnishes the student with a text book which is practically a complete repository of all that the science contains.

L. P. G.

Horse Power of Locomotives.

According to the *Railroad Gazette*, there are many cases in which 1,000 horse power and more has been exerted by locomotives. Indicator cars of Strong locomotive 444, drawing a 370 ton train at a speed of nearly 60 miles an hour, show the horse power to have been from 1,369 horse power up to 1,810 horse power. Cylinders, 20 × 24 inches; 62 inch driving wheels. Weight, 138,000 pounds, of which 90,000 pounds on driving wheels. Piston speed, 1,304 feet per minute. It is believed this power has not been exceeded.

Printing of Woolen Tissues.

Of late years the printing of woolen tissues has developed to a very great extent and has become a by no means inconsiderable branch of the textile printer's art. Consequently printers are giving much attention to it, and the printed tissues have become favorites with the ladies, who, after all, exercise a considerable influence, by creating the demand for certain textile fabrics, in developing the production of those fabrics.

There is no doubt that the great development which has of recent years taken place in the production of coal-tar colors and the many brilliant and fast dyestuffs now at the disposal of dyers and printers have contributed much toward the increased attention which has been paid to woolen printing. The woolen printer is enabled by their means to produce his effect with great ease, and with successful results, and in these respects the coal-tar colors offer superior advantages to the older natural dyestuffs. The use of these in printing presented many difficulties, and only a limited number of colors and shades could be produced by their means.

It is now customary to prepare woolen cloths which are intended to be printed on by a passage through a bath made with bleaching powder and hydrochloric acid. Dyes printed on cloth thus prepared with chlorine give colors which are much more intense and are faster than if printed on unprepared cloth. Still, although the colors obtainable on chlorine-prepared woolen tissues possess a sufficient degree of brilliancy, deft, and fastness, there are other points in connection with the prepared cloth which are not so satisfactory; thus the cloth may take a yellow tone and a harsh, unpleasant feel, and often is rather brittle. All these things are undesirable, and are no doubt due to an over-oxidation of the woolen fiber, which is not always easy to prevent. In a paper lately communicated to the Society of Dyers and Colorists, Mr. E. Lodge has shown that, by a careful regulation of the strength of the chlorine baths, this over-oxidation of the woolen fiber may be avoided and the cloth left white and comparatively soft, although its attraction for coloring matters is not less than in over-oxidized woolen cloth.


Muller has lately suggested another principle. One defect of the chlorine method is the harshness which is imparted to the woolen cloth. Now printing can be considered simply as localized dyeing, and as the color is thus produced in places on the tissue, Muller considered that the oxidation of the fiber might also be produced locally and in the places where required by the design printed on the tissue. To carry out this idea he mixes the ordinary printing color with oxidizing agents like chlorate of soda, barium peroxide, etc., with excellent results so far as regards brilliancy, intensity, and fastness of color, while the harshness of the fabric is prevented.—*Dyer and Calico Printer.*

Disinfection by Means of Sulphur.

We do not think that sufficient publicity has ever been given to the remarkable experiment made at Detroit, during a severe epidemic of diphtheria and scarlet fever, in checking the spread of the disease by disinfecting the sewers with sulphur, tons of which were burned in them. The experiment seems to have been signally successful. Of course, it would be rash to infer, from a single trial, the causal connection of things which may possibly have been simply coincident; but it is certain that as soon as the sewers had been saturated with the fumes of the burning sulphur, the epidemic declined rapidly, and both diphtheria and scarlet fever soon disappeared. The probability that cholera will make its appearance next summer in at least some of our large cities suggests the propriety of adopting this simple and inexpensive precaution, in case of the introduction of the epidemic into any sewered town. Every one knows that the fumes of burning sulphur form the most potent of disinfectants, and cholera would, in our cities, probably spread more rapidly through the sewers than in any other way. It will be remembered that at Croydon, after the introduction of sewers, typhoid fever, which had previously been endemic in the lower parts of the town, but was almost unknown in the upper regions, inhabited by the rich and well cared for people, suddenly appeared in an alarming form in the upper quarters, as if the new sewers had conducted the contagion from the abodes of filthy misery to those of wealth and cleanliness. The same thing may be expected to happen with cholera germs, which, if once introduced into the sewers, would, if they will float in the air when dried, which seems to be the case, have plenty of opportunities to escape through street ventilators, dry traps and leaky soil pipes, all over the city. The saturation of the sewers at short intervals with sulphur vapor would destroy the germs contained in them, and, it would seem, do much to localize any sporadic case, or group of cases, while no harm could be done by the operation. Indeed, the principal homeopathic prophylactic against Asiatic cholera is sulphur; so that the inhalation of a few stray fumes, although perhaps unpleasant, ought to make the person into whose nose they accidentally penetrated feel himself doubly protected.—*Amer. Architect.*

A FAN ATTACHMENT FOR ROCKING CHAIRS.


This is a device to be applied to a platform rocker, and, as one rocks backward and forward, a continuous rotary movement will be imparted to a fan held above the occupant of the chair, affording a constant and refreshing current of air. The improvement has been patented by Mr. Horace M. Baker, of No. 203 Macon Street, Carthage, Mo. The larger view shows the application of the attachment to a chair, parts of which are broken away, while the smaller view represents the details of the mechanism. At the back of the platform is

**BAKER'S ROCKING CHAIR FAN.**

the drive shaft, a crank arm on which is adjustably connected with a pitman whose upper end is pivoted on the back of the chair. On the drive shaft are also two other crank arms extending in opposite directions, each being connected by a rod with the crank arm of a different segmental gear on another shaft, so that, when one segmental gear is rotated downward, the other has an upward direction. By means of loose pinions, a ratchet wheel, and spring-pressed dogs, these opposite movements are made to impart a continuous revolution to a central shaft journaled in bearings transversely of the platform. On the outer end of this shaft is a crown wheel or gearing meshing with a pinion on the lower end of an upright fan shaft journaled at one side of the chair, the fan shaft carrying on its upper end a fan, the blades of which may be made, if desired, to open outward as a person is seated, and automatically fold down around the shaft when the chair is vacated. The fan shaft may be also entirely removed from the chair. With this attachment in position, the fan is kept constantly in motion while the occupant of the chair continues to rock.

AN IMPROVED GANG SAWMILL.

The gang sawmill shown in the illustration, although it may be adapted for sawing different kinds of material, is especially designed to saw shingles, operat-

**MACREY'S GANG SAWMILL.**

ing two gangs of saws in such a way as to saw up an entire bolt at one operation, without waste of stuff, the saw gangs being independently adjustable in relation to each other to give the desired pitch or bevel to the shingles. The improvement is the invention of Mr. William T. MacRey, of Vancouver, British Columbia. Each frame, with its gang of saws, is reciprocated in the standard by a pitman, connected with a crank on the driving shaft; the frames being arranged in their guides so that the wear may be readily taken up. One saw frame slides vertically in the standard, and just behind it the other saw frame slides in inclined guides, so that its saws will be at a slight angle to those in the first frame, the guide frame being quickly and accurately adjusted by the set screws projecting through the sides of the standard. In operation, one frame goes up while the other goes down, the vertical saws cutting the bolt into straight strips and the oblique saws then cutting these straight pieces to the desired pitch or bevel. At a convenient height for the insertion of the bolts to be sawed the standard has projecting portions, one above the other, which form supports for upper and lower feed bars, adapted to move back and forth at right angles to the saw frames. These feed bars have teeth in their faces to engage the bolt, and move toward each other to clamp it in place, reciprocating to feed the bolt through the machine, the lower feed bars being lifted upward and thrown forward, while the upper ones are thrown downward and forward. The inclined guides may be arranged vertically if desired, so that the bolt may be sawed into staves of uniform thickness. It is said that this sawmill, cutting shingles, will cut from three hundred to four hundred thousand per day of ten hours.

This improved mill is being placed on the market by the MacRey Patent Gang Mill Co., of Vancouver, Toronto, and Buffalo.

Rubbers.

I know it is the custom and the habit to sneer at rubbers. It is the custom and the habit to say: "Why don't you give us something that is good for something?" We give you, gentlemen, just what you called for. I will guarantee that in my mail (and we average perhaps a hundred letters a day) there is not one letter out of 5,000 which says: "What is the best thing you have got?" but it says: "What is the cheapest thing you have got?" Now, when you ask for the cheapest thing, we are going to give you lampblack and whiting and resin, and everything else that will make the goods cheap. When you turn around and say: "Give us good rubbers that will pull and stretch and hold," and pay for them, we will give them to you; and we won't give them to you until you do ask for them.

We are glad to see you gentlemen here as representatives of the trade. No gentlemen can get together in any one line of trade and rub their heads and ideas together without imparting knowledge to one another. We take more in by absorption than by reading and study.

I want to say to you, gentlemen of the national association, that if you never accomplish another thing, the fact of your establishing what is recognized throughout the United States, and almost throughout the world, the standard measurements, is a monument to your enterprise and your energy. There is not a manufacturer now that goes to work to make shoes but what consults that standard. It is the standard. There is no standard among us rubber fellows. I expect you will go for us next. But that is a very difficult thing to accomplish, more difficult than you have any idea of. You sell a woman a pair of shoes, 4 D, and you think a 4½ rubber ought to fit her. Perhaps it will and perhaps it won't. If it is a grain button boot, it won't fit. If it is a square edge, it won't fit; if it is a bevel edge, it will. Then you want to recollect that the lasts upon which the rubbers are made are put into a heater. They are all supposed to be made out of upland maple. Well, these dear countrymen get the maple out for us, and sometimes we find a good deal of swamp maple in it. That is put into a heater, 268° F. The heat will affect one piece of wood in one way and another piece in another.—*W. L. Sage.*

Storage Battery Monopoly.

After a struggle lasting for about ten years, beginning in the Patent Office and carried successively through the United States Circuit Courts in several States, the United States Circuit Court of Appeals on the 4th inst. handed down a decision sustaining the decree of Judge Coxe rendered in July, 1891, in the suit of the Brush Company against the Electrical Accumulator Company. The sole right to use storage batteries with the active matter mechanically applied is now owned by the Consolidated Electric Storage Company, the licensees of the Brush Electric Company. Consequently, this decision gives to the Consolidated Electric Storage Company a monopoly of the storage battery business throughout the United States for a period of over ten years next ensuing.

The Electrical Salesman.

Perhaps no other industry has developed so many peculiar conditions surrounding the disposal of its product as has the electrical field. A unique genius is the fruit of this set of conditions. The genius is known as "the electrical salesman." The causes for his being have been natural only to a certain extent. There were things, peculiar things, to be disposed of by barter and trade to the people, and some one had to be found to do it. The electrical salesman was not born—he has evolved.

In ancient days, ten years ago, the difference between the office boy and the electrical salesman was merely one of age; each knew about as much regarding electrical apparatus and its sale as did the other. But as the business grew, conditions arose which acted as the pyro solution on a photographic negative—they developed. Existing manufacturing companies attained greater proportions, alliances with other companies were made, contracts were drawn up, sub-contracts were let and relet, territories were defined, cut, recut and defined all over again, price lists changed nearly every hour, and at last combinations, consolidations, and complications (for the salesman) were effected, bringing us down to the present day, and all the time competition kept getting keener. During this tremendous advance the factories were belching forth thousands of tons of all kinds of electrical apparatus, which must be disposed of. It was then that the electrical salesman began to evolve. He was the all-important medium between producer and consumer, employed to tell

the merits of apparatus to the buyer and to report defects, as they came under his notice, to the manufacturers, that they might apply the remedy.

The electrical salesman, in all truth, has been the factor on the commercial side of electrical development: he is the king pin of the electrical car of progress. He has been maligned, insulted, given the lie, and generally maltreated by the public at times, but only at times, because he has many friends, and deserves more. It is only the absurd few who do not understand his genius that have abused him, and

even these few, we dare say, will change their opinions of him ere long.

There are many electrical salesmen who hold responsible and valuable positions to-day, all owing to the experience acquired during their evolution. These will move up higher and others will follow along after them. It is probably true that nine-tenths of our electrical brethren have been or will be salesmen before they die.

To be the *beau ideal* of electrical salesmen, a man

course to expedients to overcome his competitors. As we said before, an electrical salesman is not born with all these attributes of genius, but he assimilates them as he evolves and ends by surprising himself at his own abilities.—*Electrical Review*.

APPARATUS FOR MANUFACTURING AND LIFTING BLOCKS OF BETON AT THE PORT OF BILBAO.

As the method of manufacture of the blocks of beton used in the construction of an external port at Bilbao, and the apparatus employed for lifting and carrying them, present some novelty, we propose to enter into some detail upon the subject.

The beton apparatus, constructed by Carey & Lathan, an English firm, consists of a cylinder 3 meters in length and 0.91 meter in internal diameter, movable around its axis, which makes an angle of about 3° with the horizontal. In the interior of this cylinder there operate sixteen helicoidal paddles fixed upon a tubular axis, which makes fifteen revolutions per minute, while the external cylinder makes twenty. Into the interior of the latter, two chains of buckets, though lateral hoppers, empty the stone and sand in the proper proportions. The cement is put into a hopper placed upon a covered platform, whence it is taken up by a screw and carried to the interior of the cylinder in which the beton is under preparation. The velocity of this screw is independent of the general motion of the apparatus. It is so regulated that the quantity of cement that it introduces into the cylinder may be varied at will.

The materials, that is to say, the stone, sand, and cement, enter simultaneously at the top of the cylinder, and, during the first third of their travel, are mixed, while dry, through the motion of the paddles and that of the external cylinder. The water, the quantity of which can be regulated at will, enters continuously through a tube that debouches in the second third of the length of the cylinder, so that the elements that form the beton are intimately incorporated before leaving the apparatus. When finished, the beton falls into Decauville cars, which carry it to the spot where the blocks are to be manufactured. The




Fig. 1.—WORK AT THE PORT OF BILBAO—FRAMEWORK AND APPARATUS FOR LIFTING BLOCKS OF BETON AND LOADING THEM ON A BARGE.




Fig. 2.—FRONT VIEW OF THE APPARATUS FOR LIFTING BLOCKS OF BETON AND CARRYING THEM TO THE CAR.

should begin with perfect confidence in himself, supreme assurance as to his certainty of victory, and a *quantum sufficit* of technical knowledge. In addition, he must possess the detective's instinct in ferreting out "jobs," the reporter's "nose for news," so that he will know a customer when he sees one, an ability for making and keeping friends, good conversational powers, the wiles of a diplomat, the silver tongue of an orator, and the sincere and convincing arguments of a practiced debater. And he must be always resourceful and ready at any and all times to have re-

sand, and cement, enter simultaneously at the top of the cylinder, and, during the first third of their travel, are mixed, while dry, through the motion of the paddles and that of the external cylinder. The water, the quantity of which can be regulated at will, enters continuously through a tube that debouches in the second third of the length of the cylinder, so that the elements that form the beton are intimately incorporated before leaving the apparatus. When finished, the beton falls into Decauville cars, which carry it to the spot where the blocks are to be manufactured. The

apparatus is capable of furnishing from 15 to 18 cubic meters per hour, and this permits of manufacturing four blocks of 50 cubic meters or seven of 30. The power of the motor is 18 horses.

The contractors arrange upon the platform for preparing the blocks 517 moulds, 120 of which are of 50 cubic meters and 397 of 30, representing a total volume of 17,910 cubic meters. With the method of carrying that they employ, they are capable of submerging, in a period of three months, all the blocks that the platform can hold.

Let us now pass to the apparatus employed for lifting, carrying, and shipping the blocks.

The frame of the rolling crane for lifting the blocks consists of two strong trestles of plate and angle iron connected at the upper part by two cross pieces that support a flooring 2.6 meters in width, upon which is installed the entire motive mechanism. This crane is provided with four pairs of wheels and runs upon tracks of 5.7 meters gauge formed of Vignole rails supported by strong wooden ties. It differs but little, as a whole, from the cranes that have hitherto been constructed for the same purpose; but up to the present only manual or steam power has been used, while in this case it is electricity that actuates the lifting and shifting mechanisms and that gives motion to the various apparatus serving to carry the blocks to the place of shipment. To this effect there is installed at a certain point of the field of operations a dynamo actuated by a 60 horse power compound engine making 800 revolutions per minute. This dynamo develops an e. m. f. of 220 volts and produces a current of 200 amperes. The e. m. f. is transmitted by a non-insulated copper wire strung upon wooden poles. This conductor is established all along the beton yard, and the current may be received by the dynamo carried by the rolling crane, whatever be the spot occupied by the latter upon the tracks. To this effect, upon the sides of the platform there are two bamboo canes 3.6 meters in length movable around a joint situated at 1.1 meters from the lower extremity.

At the upper part of each bamboo there is fixed a small iron pulley which bears constantly against the wires of the circuit, owing to a counterpoise at the base of the bamboo canes. Communication between these pulleys and the receiving dynamo is established by means of copper conductors covered with gutta percha. The circuit is closed through this dynamo. The current traverses a resistance apparatus which allows of the passage of the whole or a part of the e. m. f., according to the work to be effected.

The receiving dynamo makes 600 revolutions per minute, and effects the rotation of a horizontal shaft that transmits power either to the pistons of the hydraulic presses that serve to lift the blocks and that have a maximum stroke of 0.4 meter, or to another horizontal shaft situated at right angles with the other, and upon which are mounted pinions that gear with two endless chains. The latter transmit the power to drums fixed to the front wheels of the crane. These wheels produce the motion of the entire apparatus upon the tracks at the velocity of 10 meters per minute.

The pistons of the hydraulic presses are connected by joints with the hooks that serve to suspend the blocks. The length of the hooks varies with the size of the blocks to be lifted. Each block carries two lewisons, that are set into the block at the time of its manufacture, and with which the suspension hooks engage.

When the apparatus is placed over the block to be lifted and carried, the hooks are introduced into the lewisons, then the machine is set in motion, and the suction pipe of the pump is opened in order to allow water to enter the cylinders of the hydraulic presses. As soon as the pistons of the latter have lifted the block about 30 centimeters, the pipe is closed, and the wheels that control the motion of the crane upon the rails are thrown into gear. The crane, once in motion, is led over a truck or car that runs upon a transverse track. At this moment, the cylinders of the presses are

emptied and the block slowly descends upon the platform of the truck. This operation finished, the hooks are disengaged and the crane moves backward over another block, which it carries to the truck as before.

The truck or car that carries the block is likewise moved by electricity. To this effect, it is provided with a receiving dynamo analogous to that of the lifting apparatus. This dynamo receives the current through copper wires. The latter are not insulated, so that at every point of their length communication may be established with the receiving apparatus and the circuit be closed through the generating dynamo.

This car is hauled under a framework consisting of two strong horizontal iron trusses supported by cross-braced wooden posts, each surmounted by a cast iron cap. The bases of these posts are set into masonry. At the upper part of the framework is situated the apparatus designed to lift the block and bring it directly over the lighter that is to carry it to the point where it is to be submerged. This apparatus is set in motion by electricity. It is constructed upon the same prin-

the battery would carry the load about 100 miles without recharging. In spite of some delays at the various switches, the average running speed was about 12 miles an hour, and the best mile was done in 3:35. The trial seems to have been very satisfactory.

Fibrous Clay.

Clay, in every respect, resembles very closely the fundamental and natural principles of oxides and ores of metals, and maintains the same characteristics with remarkable relations all the way through its formation after manufacture. But the closest of all metals of which it assumes similarity is iron.

For example: Iron ore ground and smelted and cast into pig metal is short or brittle, not having any particular grain, except slightly lengthwise, the way the metal flows in casting. If this same pig metal is reheated into a workable or pliable condition, and put under rollers and for a number of times rolled in the same direction, then by compression the crystals, which in dimensions are almost equal in every direction, and join only at geometrical points, are being first flattened, then drawn or pressed oblong. The process of cooling again acts upon them to slightly separate the crystals, but leaving them in groups closely adhered to each other, and wherever these breaks or contraction cavities occur there will take place a sliding of the particles upon each other in the process of rolling.

The effect of this is that the construction of the original pig metal, which appears much like compressed salt, becomes a series of fibrous-formed material, overlapping each other like brick masonry, excepting that the longitudinal sections are probably hundreds of thousands of times smaller in diameter.

In many instances the formation of rolled iron may be compared with oak timber in its formation of grains or fibers, which has at the same time throughout its longitudinal structure a large amount of cross fibers.

Comparing the same with the continuous working of the clay into one direction produces the same effect of forming a fibrous grain as can be seen in a bar of rolled iron. For instance, take a sewer pipe when it first comes from the press; it would be difficult to tear it sideways, while it can be torn into small shreds lengthwise, the course it passed through the die. The same with a brick being made on a spiral or plunger brick machine. If the brick is an end cut, it will be almost impossible to break it evenly crossways, while there would be but little trouble to split it lengthwise into any number of parts. Therefore, in bricks which are expected to carry much transverse strain, the lengthwise grain is much preferable over all others.

In the forming of grain in clay, water plays a very important part. As the wedging of the clay goes forward, the molecules of clay become closer attached to the moving particles, and the water and air find their way into the horizontal layers, forming the lubricator between the strata.

This is easily witnessed by a simple practical experiment. If a block of plastic clay of about twenty-five pounds be taken and rolled for several times in one direction, forming the grain in length, then the block set on end, and slabs cut from it about one inch thick, will make tiles about 9 in. x 9 in. x 1 in. in size. If these are put to dry, the probability is that 90 out of 100 will crack through the middle; the same as if a slab be cut off the end of a log crosswise, which would be sure to go to pieces before it became dry.

On the other hand, if the clay slabs or tiles were cut from the side of the former mentioned blocks, the effect of rapid drying would simply be warping, the same as a green board would turn up if placed in the sun.—*Clay Journal*.

A NEW aluminum alloy, with titanium, is made in Pittsburg. It sells at from 25 cents to \$1 per pound more than pure aluminum. It is an excellent material for making tools. About 10 per cent of titanium is used.




Fig. 3.—SIDE VIEW OF THE LIFTING APPARATUS.

ciples as the other lifting apparatus, but its frame is not of so large dimensions, and the stroke of the pistons of its hydraulic presses is different, being seven meters.

The pumps that send the water into the cylinders and the shifting mechanism receive their motion from the dynamo that the apparatus carries with it.—*Le Genie Civil*.

The Logan Storage Battery.

The Grand Trunk Railway Company gave the Standard Electric Company permission to run an electric car over its tracks on August 23, from Milwaukee Junction, near Detroit, to Mt. Clemens, and return. The car was of the regular open-face type of tram car, with seats placed back to back. The car was propelled by a Shawan motor, the electricity being furnished by the Logan storage battery, 108 cells of nine plates each. This battery, by its construction, is peculiarly adapted for use where it will be subjected to jarring. The electricity with which the batteries were charged was nearly all generated on July 5. The car and its load weighed eleven tons, and the *Detroit Tribune* says that an examination made after the trip showed that

THE SANTA MARIA.

A great series of celebrations and festivities, upon two continents, in commemoration of the first voyage and the discovery of America by Columbus, was commenced at Palos, Spain, on August 3, the four hundredth anniversary of the day on which the little fleet of the great navigator set sail on its memorable quest. The little town is on the Rio Tinto, near its mouth, in the Gulf of Cadiz, and between it and the sea is the old convent of La Rabida, intimately associated with the memory of Columbus. Near by is the much larger modern town of Huelva, which has considerable export trade, and at this port assembled the Spanish vessels and those representing foreign nations also participating in the inaugural ceremonies, as the harbor at Palos did not allow the entry of large craft.

The principal feature of the celebration at this time was found in the Santa Maria, a vessel built in every respect after the original of the largest of the three vessels of Columbus. The Nina and the Pinta, the two other vessels, completing the squadron, it is expected will be constructed in time to bear a part, in connection with the Santa Maria, in the naval celebration to take place in New York Harbor next spring, preliminary to the opening of the great exhibition at Chicago. Our picture of the Santa Maria is from a drawing made for the *Graphic* by Lieutenant E. C. Villiers, of the British Navy.

It was the design that the little vessel should sail out of the harbor of Palos in the early morning of August 3, after the same manner as the first or discovery voyage was commenced; but when the sailors spread their canvas it was found that there was no breeze, and one of the gunboats was then employed to tow her toward the ocean. The Spanish vessels followed, and every foreign ship saluted with cannon as the Santa Maria passed. The war ships of foreign nations sent to represent their governments in the celebration followed the Spanish vessels. The multitudes on shore cheered in unison with the roar of the artillery. For three hours the Santa Maria followed the route along which Columbus had been wafted by a favoring breeze, and was then towed back to Palos. Huelva, which is undertaking the larger part of the celebration, was bright with flags and thronged with visitors from all parts of the world. Palos is hardly more than a memory of what it was in the days of Columbus. It was then the chief city of the region. It has since decayed, and is overshadowed by Huelva, the capital of the province. The convent of Santa Maria de la Rabida was also thronged with visitors. The convent buildings have been put in nearly the exact condition they were 400 years ago, when Columbus was a guest there. The tower of the convent, which occupies a prominent site, was probably the last object on the mainland which Columbus saw as he sailed away.

These jubilees formed the starting point for a series of *fetes*, designed to occupy Huelva, Palos, and La Rabida during the whole of the months of August, September, and October, concluding with an International Congress and the official celebrations, in which the Queen Regent, the Court, the Ministers, the Corps Diplomatique, and the provincial and foreign deputations were to take part. At Madrid, Granada, and Seville there were to be congresses, horse races, and bull fights, gala theatrical performances, historical cavalcades, and popular fairs, balls, receptions, and *sotres*. Nothing has been spared to mark with becoming pomp the role played by Spain in the discovery of the New World.

The Santa Maria of 1892 is in every respect, and in the minutest detail, a reproduction of its analogue of 1492, as it is pictured to us in the diary of the illustrious navigator. It has the same old-fashioned shape, the same primitive masts, rigging, and sails, even the same armament of falconets and mortars, halberds and arquebuses. The cabin of the commander is furnished in the style of the fifteenth century and its table is littered with maps, documents, and nautical instruments of the period. Finally, its mastheads are decorated with the royal standards of Castile and Leon, in exact imitation of the flags which Columbus planted in the New World on October 12, 1492. The vessel is manned by an excellent crew, obtained from among the fishermen and sailors of Cadiz and San Fernando, and placed under the orders of a detachment of officers of the Royal Navy. They are all in the highest spirits and confident that they will be able to conduct this vessel of 240 tons safely to New York next year, when the great celebrations are to take place here. Preliminary to that occasion it is designed that the Santa Maria will be accompanied across the ocean by a Pinta and Nina, also constructed in imitation of the two smaller caravels which formed Columbus' escort four hundred years ago. And these in their turn will be watched over by a modern Spanish squadron, which will act as a guard of honor and render them any assistance they may need, a provision whose necessity will readily be understood when we remember that the largest of the vessels had only about the dimensions of a good sized canal boat of the present day.

World's Fair Items.

Two immense search lights, which will be used to illumine the grounds next summer, have arrived at Chicago, and will probably be used for the dedicatory exercises. These great lamps weigh respectively 2,200 and 1,300 pounds, with diameters of 4 and 3 feet. The larger one will be placed on the roof of the Manufactures Building, and will, it is said, light up the Van Buren Street station, seven miles away, with the intervening space. The other will be mounted on the cupola of the Transportation Building, and will shed light on the Illinois Central tracks, to the south and west. A six foot lamp is to be put up next summer. These search lights are the largest in the world.

The fourteen principal buildings and their cost are:

Transportation Building, 5 3-5 acres.....	\$370,000
Horticultural Building, 5 7-10 acres.....	325,000
Mining Building, 5 3-5 acres.....	265,000
Electricity Building, 5 1-2 acres.....	401,000
Machinery Hall, 9 3-5 acres.....	1,285,000
Administration Building, 1 3-5 acres.....	435,000
Agricultural Building, 9 1-5 acres.....	618,000
Manufactures Building, 30 1-2 acres.....	1,500,000
Government Building, 3 3-10 acres.....	400,000
Fisheries Building, 1 2-5 acres.....	224,000
Battleship, 1-3 acre.....	100,000
Art Building, 4 4-5 acres.....	670,000
Forestry Building, 2 1-2 acres.....	100,000
Women's Building, 1 4-5 acres.....	138,000
Total.....	\$6,831,000

The Finance Committee have decided to recommend that \$150,000 be appropriated to construct a special building for educational exhibits. It will afford 160,000 square feet of space and be located east of the Fine Arts Building. This will relieve the tremendous pressure for space in the Manufactures Building, to which the liberal arts display was previously assigned.

Canada will exhibit a mammoth cheese made at the Dominion experimental station at Perth. It weighs over 22,000 pounds, and contains the curd of a day's milk from 10,000 cows. A gigantic oaken press was erected for the purpose of constructing the cheese, and 200 tons of pressure was applied. The cheese has already been pronounced perfect in texture, flavor, and color. It will be placed in the pyramid of Canadian dairy products at the World's Fair, and will afterward be cut up and sold in pound blocks, either in Chicago or in Great Britain.

Edison's Patents Sustained by the United States Circuit Court of Appeals.

The United States Circuit Court of Appeals for the District of New York, Judge Wallace presiding and Judges Lacombe and Shipman sitting as associates, on October 4 handed down a decision affirming that of the Circuit Court in the action of the Edison Electric Light Company against the United States Electric Lighting Company.

The decision of the Circuit Court in favor of the Edison held, in effect, that the incandescent lamps manufactured and put upon the market by the United States and cognate companies were infringements of the Edison patents. The practical effect of the affirmation by the Appellate Court of Judge Wallace's decision is to give a monopoly of the manufacture of the incandescent bulbs to the Edison Company, and also confer upon it the right to claim an accounting and damages for infringements from the defendant companies. The court finds that not only any known form of incandescent lamp, but probably also any possible form of incandescent lamp that can be manufactured, is an infringement of the Edison patents, and that therefore no other competing company can make such lamps without license from the Edison company.

The present production of incandescent lamps by the Edison Company is 80,000 a day. These lamps have been put forth in like volume by rival companies for several years past. When the action was begun the United States Company was allowed to go on manufacturing the lamps pending a decision of the questions involved, by executing a bond to pay damages and account for their profits to the Edison Company in case the court should decide against them. In the interval between the inception of the action and the decision of the United States Circuit Court of Appeals, the work of assessing the damages has been going on before a master appointed by the court, and is not yet completed.

Mr. Edison applied for a patent for his lamp in 1879.

The Edison patent has about three and a half years yet to run.

The *N. Y. Herald*, in commenting on this decision says:

"The decision of the United States Circuit Court, of Appeals in favor of the priority of the Edison incandescent lamp will be hailed with the greatest satisfaction by the numerous friends of the 'Wizard of Menlo Park,' apart from all consideration of the technical and legal questions involved. The decision means many millions of dollars to the Edison General Company, in which, we understand, the inventor still maintains a solid interest.

"Hitherto Mr. Edison has not been so fortunate as he deserved to be in his business ventures. His invention of a transmitter for the telephone was sold for

an annuity of \$6,000, to be paid for a period of seventeen years. The day after he had concluded this bargain he was offered \$500,000 in cash for the invention. The quadruplex system, which revolutionized telegraphy, was bought from Mr. Edison by the Western Union Company for \$30,000. By it the Western Union Company has been enabled to save a million dollars a year in wire.

"The people of all lands owe this man a vast debt of gratitude, and will not, we believe, be slow to hail the decision of the court, which gives him back his own, with loud acclaim."

Steam on the Highway.

Peter Chalmers, a farmer of Farmington, is a genius in his line. When anything new comes out he studies to see whether it cannot be adapted to use on his farm.

For one thing, he has applied helmet oil cups to greasing wagon wheels. He has a score of grain wagons, all of them supplied with these cups, and all of the wheels can be greased by means of them in ten or fifteen minutes—a job which would require an hour or more without them.

All the plowing done on Chalmers' big ranch is done with a traction engine, and during the last plowing season he ran the engine day and night, having three shifts of men. A locomotive headlight was employed to illuminate the path ahead and another was used to throw light on the plows.

Now the farmer is hauling wheat to town with his engine. He brought a load in recently and stored it at the Stockton Warehouse. There were nine wagons in the train, and each carried sixty-eight sacks of grain. Each sack weighs, on an average, 137 pounds, so each wagon load was 9,316 pounds, and the aggregate of all the wagon loads 83,844, or nearly forty-two tons.

The farmer has 30,000 sacks of wheat to haul, some of it belonging to neighbors.

"Is it much cheaper to bring the wheat in this way than it would be to ship by rail?" asked a *Mail* reporter of Mr. Chalmers.

"Well," was the reply, "I can't say positively that it is any cheaper at all, but I think it is. You see, this is only my third trip, and I haven't been able to cast up accounts yet. The wheat I'm bringing now comes from near Farmington, which is seventeen miles from Stockton, and it would cost \$1.10 a ton to get it here by rail. Some of the wheat I'm going to haul is farther away, and to transport it on the railroad would cost \$1.50 a ton. I don't think it will cost me a dollar a ton on the longest haul."

"Where does the saving come in?"

"Well, one has to load his wheat anyhow, and if he ships it by cars, he's got to unload and then load it on the cars. That requires men and time. This way all we've got to do is to load it in the field—the warehouse men do the rest. It requires only three men to take care of our train—an engineer, a fireman, and a man to look out for the wagons and see that they don't get 'hot boxes.' The only expense of hauling, therefore, is the wages of the three men and the cost of the coal used."

"But," said the reporter, "there's the interest on the money in the engine, which cost—"

"Four thousand five hundred."

"And then there's repairs and the steady wear of the machine; and you've got to have a lot of money invested in wagons. You would only need a couple of wagons to haul to the railroad, but this way you need a dozen."

"Oh, I need the wagons and the engine on the farm, anyhow," was the reply.

In further conversation, Mr. Chalmers said it would not be feasible to haul grain as he is doing except on level and good roads. The only trouble he experienced was in crossing small bridges, which he had to brace up on the first trip. The tender carries water sufficient for only twelve hours' consumption, but water is pumped into it from watering troughs along the road.

It might seem foolish to say that the wagons follow one another around corners in the same path, since as a matter of course they would do so, but people often ask the farmer what sort of gearing he puts on his wagons to make them follow the lead.

The engine can haul the train at the rate of four miles and a half an hour, but to prevent jolting the speed is regulated to about three miles an hour.—*Stockton Mail*.

Profits of German Sugar Factories.

Last year was, generally speaking, very favorable to the German sugar factories, as is shown by the following details: The Cares sugar factory, in Dirschau, with a joint stock capital of 600,000 marks, obtained a profit of 201,788 marks, out of which a dividend of 10 per cent was declared. The sugar factory at Radegast declared a dividend of 17 per cent, that at Wendersen 20 per cent, that at Zuckendorf 22½ per cent, the sugar factories at Glazig and Korbisdorf each 12 per cent, that at Camburg 31 per cent, and that at Gross-Gerau 50 per cent (in the preceding year 42 per cent).

THE PROBABLY BEST AUTHENTICATED PICTURE OF COLUMBUS.

So many widely differing pictures of Columbus are now being published and painted upon banners for display that we republish a portrait of the great navigator which appeared in the *SCIENTIFIC AMERICAN* of May 9, 1891, in regard to which Mr. Clement R. Markham, the English geographer, submits some important particulars. In a most interesting and carefully prepared paper upon Columbus, which is reproduced in the September number of the *Proceedings of the Royal Geographical Society*, Mr. Markham amplifies the story of Columbus' life through the exhaustive local researches he has made in Italy and Spain. He found the portrait of which this is a copy in a private house at Como, where it has been carefully treasured ever since it was placed there by Paulus Jovius [Giovio], a contemporary of the great Genoese admiral. Mr. Markham says:

"We gather some idea of the admiral's personal appearance from the descriptions of Las Casas and Oviedo. He was a man of middle height, with courteous manners and noble bearing. His face was oval, with a pleasing expression, the nose aquiline, the eyes blue, and the complexion fair and inclined to ruddiness. The hair was red, though it became gray soon after he was thirty. Only one authentic portrait of Columbus is known to have been painted. The Italian historian, Paulus Jovius, who was his contemporary, collected a gallery of portraits of worthies of his time at his villa on the Lake of Como. Among them was a portrait of the admiral. There is an early engraving from it and very indifferent copies in the Uffizi at Florence and at Madrid. But until quite recently I do not think that the original was known to exist.

"It, however, never left the family, and when the last Giovio died it was inherited by her grandson, who is the present possessor. I was so fortunate as to see it when I was at Como, and also to obtain a photograph of it. Here we have the head of a venerable man, with thin gray hair, the forehead high, the eyes pensive and rather melancholy. It was thus that he doubtless appeared during the period that he was in Spain after his return in chains or during the last years of his life."

A FOUR-FOOT WATER VALVE.

On January 1, 1893, the system of water supply and distribution within the limits of the city of New York will comprise over 710 miles of water mains. These are of cast iron with calked lead joints. They vary in internal diameter from 6 inches up to 48 inches, the latter being the largest size of distribution main. In the year 1893 it is proposed to greatly extend this service and to lay twenty-five additional miles of pipe. Part of this amount represents the substitution of new for old pipe; a part represents entirely new lines.

In the present system there are over 9,000 fire hydrants and 7,300 stop cocks or valves. We illustrate one of the latter, taking as typical a valve inserted in a 48 inch main in the upper part of the

city. This valve was built in Coxsackie, N. Y., by the Kennedy Valve Mfg. Co.

The valve comprises a cast iron shell, within which the gate moves up and down or horizontally, according to the way the valve is set. In the case illustrated, the movement is horizontal. The shell is in sections, with faced joints, and the parts are fastened with

eral terms a disk, somewhat wedge-shaped, so as to fit between the valve faces. At its upper end, assuming the valve to be set upright, the gate is eight inches thick. At its lower end it is four and one-half inches thick. These dimensions refer to its outer ring or zone. The inner portions are hollowed or cored out, so that the center portion is only two and one-half inches thick. The ring or face of the gate, which abuts against the composition seat within the valve, is also made of composition.

The gate is moved by a stem, $3\frac{1}{2}$ inches in diameter, passing through a stuffing box and provided with an external screw. This is attached by a transverse steel pin, $2\frac{1}{2}$ inches in diameter, to a pair of lugs on the gate. This allows a considerable amount of play to the gate, and avoids straining the stem. The nut which operates the screw is of composition. For the packing box, hemp packing is used. The cut shows the arrangement of gearing used to turn the nut.

The valve was tested as to its tightness by a hydraulic pressure or head of two hundred pounds to the square inch.

It weighs between eleven and twelve tons, and required a truck with three teams of horses to move it across the city from the river front, where it had been delivered by lighter.

Fair Logs.

Recently, says the *Pacific Lumberman*, the tug Rip Van Winkle towed down from Port Blakely to Tacoma the ten largest logs ever cut on Puget Sound for shipment in one consignment. The logs are to form part of the foundation of the State of Washington's World's Fair Building. All the logs are 122 feet long. The largest one is 42 inches square at the large end, the others being slightly smaller. This largest log contains about 1,500 cubic feet of timber, and weighs, computing at 48 pounds per cubic foot, something over thirty tons. The aggregate weight of the ten timbers is nearly three hundred tons.

One of the most interesting things about the timbers is the manner in which they will be shipped to Chicago. It will require a train of thirty-five cars to ship them across the continent, and only air brake cars will be used. The thirty-five are at the Edison shops, where ten of them are being fitted with "bunks," or cross pieces, on which the ends of the timbers will rest. It will take seven cars to carry each two logs, whose weight will be borne entirely by the first and last of the seven.

This arrangement is necessary to allow the middle five cars to swing out from under the timbers when rounding curves, their only use being to connect the end cars.

To load the timber on the cars a strong chute has been constructed at the end of the ocean dock. They will be hauled up out of the water by a Northern Pacific locomotive, and kept straight in the chute during the operation by means of a pile driver, to which their water ends will be attached with chains.

In all 174 logs will be shipped for the foundation, and the other construction material will include between 500,000 and 600,000 feet of lumber.




PORTRAIT OF COLUMBUS, BY SEBASTIAN DEL PIOMBO, RECENTLY DISCOVERED AT COMO.

bolts. Lead gaskets are introduced between the faces of the joint to supply packing.

Within the shell are the valve seats. These are made of the best quality of composition metal, and slope toward each other like a reversed wedge.

The gate which closes the valve opening is in gen-



MAMMOTH VALVE FOR WATER MAIN, NEW YORK CITY.

THE CANADIAN PLAN FOR UTILIZING THE POWER OF NIAGARA FALLS.

In the *SCIENTIFIC AMERICAN* for March 5 last we gave an illustrated article descriptive of the great tunnel works on the American side of the Niagara River at the falls, by which the gigantic water power is to be utilized. This remarkable work is now nearly completed and several new manufacturing establishments have located near the tunnel, from which power will be taken.

While so much has been done on the American side, active steps have also been taken toward the utilization of the power of the great falls on the Canadian side. The Canadian Power Company was recently organized under charter granted by the Parliament of Ontario at its last session, with the following officers: President, Albert D. Shaw; vice-president, Francis O. Stetson; secretary and treasurer, William B. Rankine.


The valuable concession of the water power privileges on the Canadian side of Niagara passed into the control of this new company, 60 per cent of whose stock is owned by the Cataract Construction Company, the

proposed. This scheme involves a tunnel, but is very much simpler and radically different in many respects from that which is now being developed on the American side of the river.

Our engraving gives a very excellent idea of the whole scheme. A tunnel is constructed directly under the river near the falls, and water is taken in from the river above by large vertical pipes, and after passing through the turbines is discharged through a short canal out under the falls and thence into the river below. At the left hand corner of the same illustration is seen a more detailed view of this tunnel. Some idea of its size can be gained by comparing its diameter with the height of the men seen in the foreground. Large Ferranti dynamos, similar in construction to those now in use in the Ferranti station at London, are to be directly driven by powerful Pelton water wheels. The size of these units has not been definitely decided upon, but they will doubtless be very large. The immense traveling cranes which are seen will be used in moving machinery to the different parts of the tunnel.

Professor Forbes, of London, and the eminent engi-

where the fabric is touched by the solution, the dye is discharged, or it might be modified, and a pattern or effect is produced on the piece. Where an irregular effect is required, the discharging agent is applied to the surface in the form of a spray or in splashes, and where a design or pattern capable of reproduction or repetition is desired, the use of one or more revolving rollers, carrying design surfaces in relief, is preferable, which surfaces apply the solution to the fabric as it is moved past the roller, and practically print the design. These surfaces are made and the roller adjusted so as not to press too heavily upon the pile. For example, they might be made of felt or other comparatively soft material, compound, or fabric, and be of a porous nature, so that they could be kept saturated with the solution from the interior of the cylinder or from any other suitable source. In some cases, when producing an irregular or splashed pattern, a roller might be employed, which would throw the solution upon the fabric in splashes of regular or irregular size, and adjusting means for increasing or diminishing the number and size of the splashes at pleasure might be provided. The strength of the discharging agent is



THE CANADIAN PLAN FOR THE UTILIZATION OF NIAGARA FALLS.

company which is now developing the tunnel scheme on the American side. It will be seen that one corporation really controls all the water power privileges on both sides of the great cataract, and has at its command a water power estimated at more than 3,000,000 horse power.

It is the intention of the Canadian Power Company to await further practical developments on the American side before determining what the character of the works shall be. It is proposed to make the Canadian side furnish the means for the transmission of power to Buffalo and other distant points. As is well known, the possibilities on the Canadian side within the limits of Queen Victoria and Niagara Falls parks, where the company has exclusive rights, are very great for the development of cheap electric power. A tunnel of less than 800 feet in length would furnish ample outlet for an intake that would develop hundreds of thousands of horse power, and all the necessary works could be constructed at a very low cost compared with the extensive operations on the American side.

Several plans for utilizing the water power on the Canadian side have been suggested by different eminent engineers, and the accompanying illustrations represent one of the most original and interesting yet

near Ferranti have both given a great deal of study to the proposed works on the Canadian side of the falls. Those in the best position to judge expect to see work commenced some time in the spring under the management of the ablest engineers in this country and abroad.

Of the complete ultimate success of both undertakings there can be no question, and electricity will here play an important part in the solution of the great problem of securing the economical transmission of large powers. We are indebted to the *Electrical World* for our illustration and the above particulars.

Ornamenting Piled Fabrics.

This relates to ornamenting cut pile fabrics, as velvets, velveteens, corduroys and such fabrics as cannot conveniently be ornamented by the ordinary process of printing. In preparing the fabrics for treatment, they are dyed with colors that are susceptible of being discharged or modified by the action of certain discharging or modifying agents which are afterward applied. To produce the required pattern upon the dyed fabric, a solution of chloride of lime or ordinary bleaching liquor is applied at the required places to the surface of the dyed fabric. The result is that,

varied to suit the nature of the dye in the fabric. In some cases, coloring matter may be added to the discharging solution, so as to color the portions of the fabric affected by the solution; and to prevent blurring or spreading of the discharging or modifying agent, heat is employed in some suitable manner, so as to rapidly dry off the solution or fix the colors.

Curious Foundations.

The *Railway Review* tells of a novel method of laying foundations in swampy soil recently employed by an American engineer. The building to be supported was a low wooden one which it was proposed to use for the storage of machinery. Casks were set in holes in the ground along the line of posts and were filled to the depth of about one foot with iron turnings. The posts were placed in the casks, which were then filled with iron turnings compactly rammed in place. A solution of salt and water was slowly poured over the turnings, under the action of which they solidified into a hard mass. The heat of the oxidation of the iron was so great that the posts were charred. This also served to act as a preservative, and to that extent the iron turnings are probably superior to concrete under similar conditions.

Correspondence.

Molecular Motion.

To the Editor of the Scientific American:

In an article copied into the SCIENTIFIC AMERICAN SUPPLEMENT of September 3, on "A Theory of Illumination," the writer says that "scientists are somewhat off the track as regards certain minor points, such as the illumination of opaque bodies." In explaining his theory of illumination he remarks:

"Go to your room at night, when all is dark, and you see nothing whatever, for the composing atoms of each object in that room are in comparative rest. But now light the gas. Immediately vibration is set agoing by the combustion, and, passing on, it agitates the atoms of every object present.

"You now look at matter made visible, not by reflected rays, as commonly supposed, but by light waves of their own creation, caused by the imparted energy. A luminous body is the source of etheric light waves, while an opaque substance is made visible by the presence of a luminous one.

"The rays of the sun reach the side of the moon visible to us, creating among the atoms of that body a violent agitation. When they strike, their office is fulfilled; their motion has been checked, and they cease to be. But now the commotion of the moon's particles imparts its energy to the surrounding ether and thence to us, giving us the delightful evenings of full moon."

I cannot agree with the writer of the above, that matter is not made visible by reflected waves of the ether, but by light waves of its own creation, caused by imparted energy from some luminous body. If our moon were a perfect sphere and absolutely smooth, we could see it only as a point of light, in the angle equal to the angle of incidence. A perfectly smooth moon, however, would be impossible, even if composed of glass, because all matter consists of atoms and molecules, and the ultimate particles have certain dimensions.

Foliage on the banks of placid water appears to be inverted in the depths below when seen from the opposite side. As the light which impinges upon the trees is scattered in all directions, we receive those rays which bound to us from the surface of the water, and get the picture in the direction of the reflected rays. What is sometimes erroneously called the shadow of ships and foliage in marine pictures is not caused by what is supposed to be the partial absence of light, but by its reflection.

St. Helena is one of the numerous islands of the St. Lawrence River. It is here where I have been very much interested the present season in watching the play of light upon the water. I have noticed the broad band of reflected light of the moon when it appeared to dance upon the ripples in the warm summer breeze, and I have seen the narrow line of reflected light from the planet Mars. In the direction of the setting sun, when the clouds have a red and golden tint, these colors are reflected upon the water. At night the river course can be discerned by the light from the sky.

Sound is reflected as well as light. While light waves are somewhat similar to the waves of water, sound waves are produced by a to-and-fro movement of the air in concentric layers from the source of disturbance. The echo, or reflection of sound, is beautifully illustrated on the Canadian side of the river, near the "Lost Channel." As the steamer passes along the perpendicular rocks of the Laurentian range, the "toots," as they strike the shore, bound back to the boat, and we get a distinct repetition of the original sound.

Molecular motion is inherent in all matter. No atom is at rest. As the undulations of the ether from the sun strike upon the surface of the earth they shake its atoms and molecules, and this motion is what gives it warmth. A portion of the waves are quenched in doing work, while the remainder are reflected. In this mode of absorption and reflection we have all the beautiful colors in nature. I cannot understand that light of its own creation can come from any other source than intensely heated bodies. The sympathetic agitation of the molecules of opaque bodies is not competent to produce this phenomenon. H. C. STILLMAN.

Island St. Helena, St. Lawrence Park, N. Y.,
September 13, 1892.

The Mount Washington Search Light.

The top of a mountain 6,300 feet above sea level seems at first sight a curious location at which to install an electric search light, and it will be admitted that few men would ever have conceived the idea of making the experiment. To Mr. L. H. Rogers must be attributed the honor of first suggesting that a search light would be an attraction on the top of Mount Washington, and that it could be operated successfully. Mount Washington, as is well known, is the highest mountain in the States east of the Rockies and north of the Carolinas, and belongs to the White Mountain range in New Hampshire. Large numbers of people visit these mountains every summer, and beautiful little towns and large hotels nestle in the surrounding valleys, most of them being situated

where a good view of the king of the mountains may be had. Access to the mountains is extremely easy, the Concord and Montreal Railroad from Boston being the most popular route, as the line runs through country abounding in fine scenery, and takes the traveler to the very base of the mountain where the Mount Washington Railroad begins. Besides affording a vast amount of interest and amusement to the mountain summer visitor, the search light, poised at this extreme elevation, is of scientific interest.

A tower has been erected on the very highest point of the mountain, 27 feet square at the base, 50 feet high, and tapers to 14 feet square at the top. It is built of eight 9 inch spruce timbers reaching from the foundation to the top, each of the floors being supported on similar timbers, and the whole tied together by iron straps and bolted, and the framework chained down to the rocks on the mountain top. The whole building was then covered by heavy planking and clapboarded on the outside; but, even with this protection, so severe are the wind and rain storms, the moisture penetrates the building and makes the condition of operating a dynamo extremely severe, the armature after a great storm being frequently saturated with moisture. The first floor of the tower contains engine, boiler, dynamo and switchboard, the whole steam plant having been furnished by J. A. Grant & Co., of Boston. It consists at present of a 30 horse power vertical tubular boiler manufactured by the Erie City Iron Works, of Erie, Pa., which works at a pressure of 80 pounds. The engine will eventually be a 25 horse power McIntosh & Seymour high pressure engine, as it is expected that current will be furnished for lighting the Summit Hotel, but at present a 15 horse power Armington & Sims engine is used. Rain-water is used for the boiler, and it is fed through a National heater by means of a small Worthington pump, which lifts the water from a tank 10 feet below. In dry weather the water is brought up in tanks by one of the Mount Washington railroad locomotives, filled from the watering tanks on the side of the mountain. The dynamo is of the Thomson-Houston spherical armature type, compounded and capable of giving 75 volts and 110 amperes. In spite of the severe conditions owing to the extreme dampness, it has given every satisfaction, and has run without a hitch from the first. The switchboard is of the skeleton type, made of wood, and contains ammeter, voltmeter, a double pole single throw 120 ampere switch for the main search light circuit and two 10 ampere switches for the 18 incandescent lights distributed on the different floors of the tower. These lamps are on two circuits, one for the upper floors and one for the engine room. Fuse blocks and lightning arresters are also mounted on the switchboard, so as to prevent any chance of accident. In the engine room and protruding through the floor may be seen the top of the highest point of the mountain. In the center of the room a red incandescent lamp burning in a vase filled with water serves to mark the position of the copper bolt inserted in the rock, which formed one of the station marks set by the Geodetic and Coast Survey during their operations now completed. The second and third floors of the tower are used as storerooms, the fourth as the lower observation room, and the fifth as the general observation and controlling room. In this room is the controlling stand, on which is mounted a standard Weston voltmeter and ammeter, resistance coils and various switches for operating the light and the motor in the base of the search light by which the projector can be turned round in any direction, and the elevation altered at will. On the roof of the tower, open to the atmosphere, is situated the search light, which was manufactured by the General Electric Company. The light is inclosed in a projector of 30 inches diameter, the largest ever made in America, and is of 100,000 candle power nom., the actual candle power of the lamp without the reflector being 20,000. Hardtmuth carbons, made specially for this work in Vienna, Austria, are used in the lamp, measuring 1½ inches diameter for the positive and 1 inch for the negative, the positive carbon being cored. The reflector consists of a Mangin lens with 14½ inch focal point, made in Paris by a secret process, by which the quicksilver on the back of the reflector can withstand the extreme heat of the arc. The lamp when operating requires 45 volts and about 90 amperes, the voltage of the dynamo being reduced by resistances on the floor below.

Viewed from any of the well known summer resorts in the vicinity the effect is very fine, and it is astonishing to note the interest shown in the light by the visitors to these hotels, who gather in knots on the verandas and discuss the all-absorbing topic of "search lights" and endeavor to read the messages signaled to them, by means of a code which has been distributed in thousands all over that section of the country. At Maplewood, for instance, where the writer recently stood on one beautiful clear night 20 miles from the top of the mountain by air line, the light was "turned on" the hotel for about 20 minutes, and signals were read with the greatest ease and precision. At that distance the light is almost too bright to be looked at

comfortably, and the effect of the illumination on the hotel is quite marked. The time on a watch is easily told and type as large as the heading of this article read with ease. On white surfaces such as the front of the hotel a curious shimmering effect is produced, and small dark patches seem to float constantly over the surface, produced perhaps by the magnified effect of minute particles of vapor in the atmosphere, or by some other phenomenon not yet accounted for. The signaling is accomplished by a metal damper in the inside of the projector which can be lowered between the arc and the lens by a lever extending to the outside, and by means of which flashes of short or long duration can be effected. At Maplewood, on the night when the writer was present, several signals were given and readily interpreted. Before spelling out the words, ten short flashes were given to attract attention, and then came a series of long and short flashes, spelling out the words of the famous message which will go down to all posterity as being the first telegraphic message ever sent by the Morse telegraph: "What hath God wrought!" After each word, the beam of light is moved up and down, and at the conclusion of the sentence a circular sweep of the beam shows that the message is concluded. A few minutes later the words: "Maplewood Hotel, good night," came flashing through the air, and one felt as if on personal terms of friendship with the friendly beam shedding its pure light over the intervening miles of rocky glen and wooded hillside. At Fabyan's, eight miles from the top of the mountain, ordinary type can easily be read, and at Mr. Milliken's Glen House, which is only five miles away by air line, the light makes the grounds as light as day. Standing alongside of the projector on the top of the tower at night, the sight is also a very grand one, and a beautiful view of the beam of light can be had.

When the projector is turned in the direction of any of the portions of the mountain from one-half to one mile away, the effect is very pretty, as it makes a round circle of light, and shows up any particular object even more distinctly than by daylight. It is a great source of pleasure to the visitors and they never seem to tire of watching the different effects produced. That it is a great attraction in the mountains is amply proved by the fact that in small places where the lights of the village cannot be seen by the naked eye from the mountain top, large bonfires are nightly kindled in the hopes that the ray of light will be turned in their direction. Many letters and telegrams are also received daily with "special requests for the search light," and letters from many eminent men within a radius of 100 miles have been received stating that the light had been seen and asking for further experiments in their particular directions.

As to the distance from which the light has been seen, it is a little difficult to get accurate figures. At Portland, which is 85 miles away, the beam of light has been distinctly seen, and actual telegraphic conversation held with the operator on the mountain, the search light flashing out a message, and the telegraphic operator at Portland repeating it by ordinary telegraph back to the mountain. Many towns 100 miles away have reported seeing it, and one report states that it was seen on one occasion at Pigeon Cove, Cape Ann, on the coast of Massachusetts, a distance of 116 miles. Recently the New England district of the Weather Bureau has instructed Mr. Rogers to make experiments on weather signaling, and for the past three weeks weather signals have been shown at eight o'clock every evening to the surrounding districts, a combination of long and short flashes signifying fine or rainy weather, according to the reports from the bureau. These signals have been seen and read at Exeter, N. H., a town about 100 miles from Mount Washington, and are giving general satisfaction to the surrounding countryside.—A. C. Shaw, in the *Electrical Engineer*.

Only Man Ever Killed by a Meteor.

To the writer's certain knowledge there is but one case on record where a human being has been killed by an aerolite or fall of meteoric stone. The fatality mentioned occurred in Whetstone Township, Crawford County, O., in 1875, and is recorded in the *Bucyrus Journal* as follows:

"As David Misenthaler, the famous stockman of Whetstone Township, was driving his cows to the barn about daylight this morning he was struck by an aerolite and instantly killed. . . . It appears as if the stone had come down from a direction a little west of south, striking the man just under or on the right shoulder, passing obliquely through him from the right shoulder to just above the left hip, burying the greater portion of his body under itself in the soft earth. The stone is about the size of a wooden water bucket, and appears to be composed of pyrites of iron."—*Philadelphia Press*.

[The item quoted by our contemporary the *Press* was a canard. It was published at the time stated in the *Bucyrus Journal*, and was manufactured by one of the reporters of that paper. No such occurrence took place.—Ed. S. A.]

The Chicago New Drainage Canal.


August saw the actual beginning of one of the largest engineering schemes in the country. For many years Chicago has had spasmodic attacks of realizing that her sewerage system was inadequate to her needs. After each fresh attack improvements have been planned and executed, which, however, were only of a temporary nature, owing to the ever-increasing size of the city. At present, with every severe storm the sewers are flushed out into the river, and with any heavy fall of rain a few miles back in the country the low river valleys are flooded and the waters come rushing down into the South Branch of the river, driving all its dangerous pollution into Lake Michigan. Pumping works have from time to time been established to induce the beautiful Chicago River to change its nature, and, unlike most rivers, be able to flow two ways. These pumps are no longer powerful enough, and for the last five years there has existed a drainage commission whose history is more stormy than that of the Guelphs and Ghibellines, but which has now either killed off its most belligerent members, has lost its fighting blood, or at least appears to be devoting itself in a somewhat more energetic manner to drainage and less to lively discussions of a somewhat political character. The present scheme is to create a channel from Lake Michigan, at Chicago, for a distance of forty miles to Joliet. The route of this channel will lie chiefly through the valley of the Des Plaines. Starting from one of the southwest "tributaries" of the Chicago River, it will, in its westward course, utilize the Illinois and Michigan canal, create new cuts, and finally settle itself into the bed of the Des Plaines, widened and deepened to suit its needs. In time the current will reach the Illinois River, and by this waterway will eventually gain and mingle with the floods of the Mississippi. The one saving feature of the scheme for the counties adjacent to Cook County, and in fact for part of that same county itself, lies in the fact that the land surrounding the lake is considerably higher than that several miles back in the country, and consequently sufficient fall can be secured in the channel to obtain for it a large volume of water from Lake Michigan. That the towns along the route of this channel, into which Chicago intends to pour all of her liquid and semi-liquid filth, should have for an hour entertained the idea of permitting such an enterprise seems incomprehensible. Such, however, in the main is the idea of the present great drainage undertaking of Chicago. There is talk of eventually constructing the channel so as to make it navigable for large vessels, thus making Chicago, as well as the smaller towns along its course, in a degree, seaports, giving them direct connection with the Atlantic.

The law requires that the channel must be two hundred feet wide at the surface, one hundred and eighty feet wide at the bottom, with a depth of water of eighteen feet. The flow of water must be at the minimum rate of three miles an hour. These conditions are required, not because of any question of navigation, but that the sewerage may be sufficiently diluted to render it harmless and inoffensive. Experience and experiments in various countries have shown that twenty thousand cubic feet of water a minute is the least amount that, by diluting, can render harmless the sewage from a city of one hundred thousand population. The plans will contemplate the possibility of the growth of the city during the next thirty years up to the number of three millions in population; and, consequently, the channel will provide for a possible flow of six hundred thousand feet, or three times the original estimate. Not all the water sufficient to dilute the sewage can be carried through the South Branch, and another channel from the lake will have to be created, to enter the main channel at a point farther west. As consent to carry the drainage canal through the west-lying towns has been obtained from the inhabitants, conditional upon the amount of pure water brought into the channel, and this permission would be canceled if any lack of the fresh water supply arises, it appears probable that the requirements will be fulfilled. Though this sketch of the plan contains the chief elements embodied in the scheme, there are many minor details yet to be arranged. The ceremony of breaking ground for the main channel has already taken place, accompanied by the usual amount of flourish. When this great undertaking is finally completed, Chicago will have a system of drainage to be proud of, with a

lake unpolluted by the drainage of a great city. The result will be most important, not only to the sanitary condition of the city, but will be the means of adding not a little to its beauty, so far as its water surroundings are concerned.—*Amer. Architect.*

AN INTERESTING TOY.

We give engravings of a toy bugle provided with an air chamber divided into two compartments, in one of which is placed a disk having a series of radial slots covered by reeds. In the partition is an aperture through which air passing through the reeds can find its way into the rear chamber. In this chamber, on the prolongation of the axis of the reed disk, is placed

**HORN WITH REMOVABLE REEDS.**

a ratchet wheel, and on the same axis is pivoted a lever which extends through a slot in the casing. The lever carries a spring pawl, which acts upon the ratchet wheel. An induction pipe communicates with the chamber in which the reeds are located, and an education pipe with a flaring end is connected with the chamber containing the ratchet. The disk is revolved by vibrating the lever, causing the pawl to engage the teeth of the ratchet wheel in succession. By means of this movement, a step-by-step motion is given to the disk which brings the reeds in regular succession opposite the opening in the partition, so that one after another of the notes of the music represented by the different reeds are produced and the tune is played. At the end of the tune there is a blank space, which prevents any sound being made, and this notifies the player to stop, unless he wishes to repeat the tune.

In Figs. 4 and 5 is shown a disk carrying removable reeds, which admit of changing the tune by simply drawing out one set of reeds and inserting another set. The construction of the reeds is shown in Fig. 6, while the arrangement of the lever, ratchet wheel, disk and apertures in the central partition is clearly shown in

insoluble lake which colors the fibers of the cloth with a more or less insoluble and fast color. This at once removes any danger in the wearing of the material. As a matter of fact, arsenic colors contain a considerable excess of alumina, and this is a preventive against the possible presence of uncombined arsenic. In extract alizarine colors, the soluble arseniate of alumina is sometimes added to brighten the colors, but, on steaming, the insoluble compound is obtained. When used properly, there is no harm in the use of this drug, and the cry which, no doubt, has been the cause of a decline in some classes of prints has originated from experiments on a small scale and conducted on false premises.

Colors.—Auramine is a coloring matter which gives a very pure shade of yellow, whether dyed on yarn or printed on calico; for yarn, chrome yellow is, however, cheaper and more readily produced. Auramine has all the advantages of aniline yellows without their deficiencies, as it is moderately fast to soap and light. If dyed by means of alumina, a good green shade is obtained, but it is loose; when fixed with sumac and tin, or tannic acid and tartar fustic, a most beautiful shade of pure maize yellow is obtained. The more tannic acid employed—up to the limit of 12 ounces good tannic acid to 3 ounces auramine—the faster will be the yellow obtained, but it must be observed that the color is not so bright as when less tannic is used, because the brown dulls the yellow. The same must be understood with equal force as to the use of auramine in printing, where a fine color can be obtained by fixing the auramine with 12 ounces per gallon of pure tannic acid and from 3 to 4 ounces auramine; this will stand strong soaping, but not so well as *berry yellow*. Auramine is, at present, largely adopted in many styles, as it is much less difficult and a more regular color to work than the *berry yellow*, and it will work well with many aniline colors. A yellow shade of green is got from it, and aniline crystal green. To detect it on the fiber, the following tests are reliable: Caustic soda turns the color white very rapidly; dilute hydrochloric, same result. It can be readily ascertained whether the color is fixed with tannic acid or alumina by boiling a piece of the cloth in a dilute solution of chloride of iron. Blackness will show tannic acid. A very fine shade of yellow, possessed of extraordinary *fastness*, in fact, the fastest artificial color as yet discovered, is chrysamine, used very much in dyeing, rarely in printing. It is not materially affected by acids, soap, or alkalies, and even caustic soda, light, air, rubbing, or chemie have little effect, except that alkalies turn it to an orange shade, while acids will restore it to a pure yellow, with a slight tendency toward light green. The present prevailing features in some print dress goods of pale yellows and buffs, as well as in cotton hosiery and laces, are produced by chrysamine, or mixtures of it, with benzo-purpurine and other *azo* colors. In dyeing, the shade is obtained at one bath and without a mordant operation, etc., necessary in other dyes, and which are so injurious to the fiber of fine cotton lace goods. The

reason the use of this dye is so much restricted is that a deep shade of yellow cannot be obtained so far. It is, however, found useful for buffs, and every delicate shade of pale yellow, salmon, etc.; it is not readily soluble in cold water, but dissolves freely in hot, and is still more soluble when in boiling water with a small atom of caustic soda. There is little doubt that this is the yellow of the future, when science unfolds nature's mystery.

Metallic Tungsten.

Dr. Martin Krieg, of Magdeburg, prepares pure metallic tungsten in the following manner: The finely ground tungsten


**DETAILS OF THE MUSICAL HORN.**

Fig. 4. A person who is not a musician may play upon this instrument as well as the best player.

Cotton Manufacture.

Arsenic in Prints.—A large proportion of prints contains small quantities of arsenic—so small, in fact, that there is not the slightest cause for alarm. Many of the anilines, such as ceruleine blue, aniline greens, etc., and many of the vegetable colors, are fixed on calico by printing the color with a salt of alumina and a solution of white arsenic in glycerine, or in a borax solution. The reaction that takes place on steaming the goods is a double compound of arsenic, alumina, and coloring matter or, briefly, double arseniate of alumina and dye. This compound constitutes the

mineral is made into a porous mass with fine carbon and tar or pitch. This mass is placed in the voltaic arc of the Jablochkoff system and chlorine introduced through the hollow candles. The candles can be made to furnish the chlorine by adding chloride of lime and silica to the material from which they are made. In either case chloride of tungsten is produced together with chloride of other metals.

If these chlorides be boiled in concentrated hydrochloric acid, oxide of tungsten is thrown down; the other chlorides are dissolved. The oxide is separated by decantation and washed. This oxide, mixed with carbon, can be easily reduced in the voltaic arc in an atmosphere of neutral gas.

RECENTLY PATENTED INVENTIONS.

Railway Appliances.

CAR COUPLING.—Eugene Geant, Fort Logan, Col. On the laterally-swinging longitudinally-yielding drawhead provided by this invention is pivoted a clasp having an eye and depending flaring flaps, the prongs of the clasp when it swings downward locking the coupled drawbars, the outer end of each of which has a rounded-off end and an inclined shoulder adapted to engage a similar shoulder on the opposite drawbar. The device permits an easy coupling and uncoupling without the operator passing between the cars, and each head is adapted to receive an ordinary coupling link to be coupled with a car having the ordinary link and pin coupling.

SIGNAL AND STAND.—George T. Brown, Sedalia, Mo. This is an improved device for carrying signal flags on the front part of a locomotive. It consists of a cylindrical column containing several tubular chambers, and with an outside socket at its base, the flags of different colors, rolled on their staffs, being kept in the chambers, for which there is a removable cap piece, having also an outside socket. The latter socket and the one in the base form supports for the staff of the flag being displayed.

Mechanical Appliances.

ELECTRIC MOTOR.—William M. Dresskell, Brainerd, Minn. This motor may be operated by an alternating or direct current, the sections of the commutator being readily removed and replaced without disarranging the adjustments of the machine. A multipolar field magnet is formed of laminated circular segments held in position by clamping rings and bolts, the multipolar armature having a less number of poles than the field magnet, while the commutator is formed of a series of disks with their contact surfaces arranged with reference to the poles of the armature, to reverse the polarity of the armature as many times during its revolution as there are field magnet poles. A simple and efficient switch is provided for reversing the current in the field magnet.

WATER MOTOR.—William E. Seelye, Brainerd, Minn. This wheel has an outer rim divided into a number of curved buckets, having their larger openings inward, from which direction the water enters, the discharge being through the outer or smaller ends, the force of the water being applied near the circumference of the wheel. Means are provided for delivering the water in solid columns to the wheel buckets, and the invention includes a peculiar form of gate which enables the motor to be easily and nicely controlled.

FLUME GATE.—Stephen M. Irvin, San Bernardino, Cal. This is a gate of simple and durable construction, arranged to prevent leakage and to permit of conveniently cleaning the flume in case the latter is clogged with sand. The improvement consists of a cap adapted to close an opening in the bottom or side of the flume, a spring lever connected with the cap being pivoted on the flume and at all times pressing the cap securely in position to prevent leakage. The cap is moved to the side of the opening to clean the flume.

CHAIN WRENCH.—William H. Brock, Brooklyn, N. Y. This wrench has a convex shoe and a concave pipe-receiving depression in the rear of and adjacent to the shoe, there being a chain pivotally connected with the wrench body at the rear end of the depression, which extends transversely of the wrench completely from side to side and of a length to accommodate the pipe and cause the latter to tighten the chain when the pipe is brought from the concave depression to the forward position on the convex shoe. The wrench is strong and light, may be cheaply produced, and possesses practical advantages in being narrower than such wrenches usually are, while having the strength of a broader tool.

COUNTERBALANCING COLLAR.—Watson T. Webb, Salt Lake City, Utah Ter. This is an improvement on a former patented invention of the same inventor, relating to combined eccentric counterbalancing collars and shaper guards, and is especially adapted to counterbalance the cutters or the spindles of wood-working and other machines. The collar is secured on the cutter spindle, and a series of weights is held adjustably on the collar, lighter or heavier weights being used to compensate for the increased or decreased weight of the cutters on the head.

ROTARY MACHINE REVERSING MECHANISM.—John G. Johnson, Chester, Pa. This invention is distinctive in the fact that the driving motion is always taken from one or the other of two loose pulleys on opposite sides of an idle pulley fixed on its shaft. Only a single belt is required, and in driving either one of the loose pulleys it is made to lap partly over on the middle or idle pulley, so that only a small range of movement is required for shifting. The improvement is designed more particularly for imparting an alternately reversed rotation to the revolving shaft of steam washing machines.

PULP GRINDING MACHINE FEED.—Albert H. Lefebvre, Watertown, N. Y. This is a hydraulic feed for wood-pulp grinding machines for making paper pulp from wood blocks, and is arranged to quickly return the follower after the wood block is ground up, the machine being very simple and durable in construction and designed to be very effective in operation. A cylinder is adapted to be connected at one end alternately with a water supply and an overflow, a piston carrying the follower sliding in the cylinder, while a spring presses on the piston opposite the inlet to the cylinder. All packing and stuffing boxes, etc., are dispensed with, and a quick discharge of the water in the cylinder takes place by the action of the spring on the piston.

COUNTERSKIVING MACHINE.—Michael C. Bowman, Albert F. Rose, and Cyrus B. Morse, New York City. This is a machine for shaving or beveling or feather-edging the edges of counters for boots and shoes. It has a rotary work holder, by which the

operator may replace finished counters, while others are being operated on by the cutters, the work holder being automatically raised at the proper moment to move the work out of contact with the cutters, while there is also a novel arrangement of rotary cutters which are automatically caused to traverse the counters presented by the work holder and returned for the next cutting movement.

A MACHINE TO TREAT LEAF TOBACCO.—Charles A. Snyder, Danville, Va. This is a machine for treating the tobacco preparatory to its manufacture into plug, fine-cut, smoking tobacco, wrappers, etc. The tobacco is first subjected to and thoroughly dusted in an air bath, then treated with the desired preparations and solutions, admitted by valves in nicely regulated quantities, and afterward dried, the tobacco passing by gravity through the machine. Near the discharge end of the machine is a pipe adapted to discharge dry or powdered flavoring onto the tobacco.

Agricultural.

HAND BINDER.—Arthur Morris, Rockefeller, Ill. The guide plate, held in the left hand, has a recess at its forward end and a clamping device, while a gripping implement of pincher-like pattern is carried in the right hand, having spring-pressed handles pivotally connected and concentrically curved beaks at one end of the handles. The implement is provided with a cutting blade which does not interfere with the movement of the handles or beaks. The device affords a ready means for quickly tying sheaves of grain and securely knotting the cord.

BROODER.—Charles E. Watkins, Harvard, Mass. The brooding chamber is circular, and has a surrounding casing forming an intermediate water space, there being a lamp chamber below the casing, with an off-take pipe leading from the lamp chamber, and pipes for supplying air to and discharging it from the brooding chamber. The brooding chamber is thus well ventilated and equally heated on all sides.

Miscellaneous.

MEASURING FAUCET.—Cyrus W. Steinmetz, Harrisburg, Pa. This faucet has a valve casing having a longitudinal slot on one side and a series of short slots on the other, measuring pockets being connected with the casing by short slots, while an outlet pipe opens from the valve casing, a revolvable hollow valve having aligning slots registering with the slots and the outlet pipe. The device may be arranged within any liquid-containing tank, and is adapted to draw off any desired quantity of liquor, having also a dial and indicator to tell how much liquor is to be drawn.

WAGON BRAKE.—Enoch G. and William A. Haney, Media, Kansas. The free and unobstructed movement of the brake levers, to move the brake shoes far enough from the wheels to prevent their blocking with mud, is provided for by this improvement. Longitudinal bars secured to the sills of the wagon body have downwardly extending keepers carrying pivots for the brake levers. The brake may be put on and taken off without in any way disturbing the box, straps, or sides of the box or wagon body, and relieves them of undue strain.

PREPARATION FOR BEVERAGES.—Adele S. Krueger, of Hannahfield, Lenzie, near Glasgow, Scotland. This preparation is formed of celery, dried, roasted and ground, and, when prepared as directed, is designed to be a valuable medicinal beverage in the treatment of rheumatism and nervous disorders, and as an anti-scorbutic.

CAN WASHER.—Charles H. Southard, Preston, N. Y. Extending from one side into a water trough adapted to receive the can lying on its side is a shaft on which is an expansion brush, arranged to be expanded within the can by the pressure of the can on the brush. The improvement affords a simple and efficient machine especially designed for cleaning small-topped milk cans used for shipping milk by railroad.

INSECT CATCHER.—William A. McAdams, Brooklyn, N. Y. Attached to a hoop having a handle is a conical net having at its apex an elastic bulb or pouch having a neck and an aperture for the escape of air. The net is carried rapidly through the air to follow the insect in its flight, thus forcing the insect into and through the neck of the bulb, the latter being removable for the purpose of disposing of the insects caught.

COOLING AND FILTERING WATER.—Albert Smith, Colorado Springs, Col. This invention relates to cooling and filtering water from which ice is to be made, before the water goes to the freezing cans. Solid or foreign matters are precipitated in a storage tank by suitable chemicals, a pipe leading thence through a filter to a cooling tank. The latter has a coil supplied with brine from a freezing tank, and in the cooling tank is revolved a shaft carrying agitating blades, gently agitating the water to more thoroughly subject it to the action of the cooling coil and facilitate its giving off the contained air, the air being exhausted by a vacuum pump at the top.

RING HOLDER.—Julius Smith, Tom's River, N. J. This device has a raised or hollow base having a recess in the upper side at one end, the recess having a bottom wall and a back wall with a slot, while there is a spring within the base and projecting at one end through the slot and across the bottom wall of the recess. The holder is adjustable, and designed to be arranged in a tray, case, or other convenient way to hold any kind of ring, or any kind of jewelry having a ring or loop attached thereto, holding the ring or other article in a way to exhibit it to advantage.

COAL CHUTE.—Gustavus L. Stuebner, Long Island City, N. Y. This chute consists of a tubular column with openings at intervals in its length and a hopper at its upper end, doors being hinged to swing over and from the openings, so that coal delivered to the chute may be drawn out at any desired height from the ground in sufficient quantities to provide

space above at the top for one load of coal, preventing coal from becoming broken when dumped into the chute by providing that it may fall only a short distance. Any of the doors in the chute may be readily opened from the dumping platform.

DAVIT HOOK.—Samuel B. Butler, New York City. The body of this hook slides in an enveloping sleeve, a spiral spring on the hook body engaging a projection on the sleeve and a washer plate, while a tripping nose piece is pivoted below on a lateral limb of the hook body, there being a locking device for the hook nose piece which prevents it from vibrating when it is loaded. The hook is designed to engage the block and suspending ring of the boat fall ropes, so as to automatically release the ring as soon as the weight of the suspended boat and its load is upborne by the water of floatage, a single block tackle being used as well as a single davit hook.

SACK.—Harry V. W. Stivers and James Hoagland, Camden, N. J. Sacks for holding grain are by this improvement provided with a tie which can be quickly and conveniently manipulated, and which will securely close the mouth of the sack, the latter having handles at opposite sides to facilitate moving it. The band forming the tie is attached to the sack, and has on one end a hook adapted to engage apertures, preferably eyeleted in the other end of the band as the sack is closed.

ATOMIZER.—Harley M. Dunlap, Battle Creek, Mich. This device consists of a two-part spraying tube, having a side opening in the lower member and a hollow coupling connecting the two members, the coupling having a side opening to register with the side opening in the tube. This atomizer is easily taken apart and put together, especially adapting it for use in producing balsamic sprays, the solutions of which are apt to clog spraying tubes.

FIRE ESCAPE.—Patrick Lynch, Jr., Superior, Wis. This escape has upper and lower strong hangers attached to and projecting out from the building, and in these hangers are journaled shafts carrying sprocket wheels and chains connected by rungs to form an endless flexible ladder, with steps hinged to the rungs. In addition to the steps are bail-shaped guards in which a person may rest when standing on the steps. The escape is intended to work automatically, but where the weight is insufficient to work it a crank shaft may be employed, people stepping from the window upon the escape, and the rapidity of their descent being controlled by a simple brake mechanism.

BRIDLE ATTACHMENT.—Joseph W. Peace, Rhea Springs, Tenn. The cheek pieces of the bridle, according to this improvement, have snap hooks at their ends, while a brace band is secured to the cheek pieces below the brow band, and the nose band has rings at opposite sides with which the snap hooks engage. A simple, convenient, and handsome bridle is thus produced, which may be quickly and easily changed from a blind driving bridle into an open riding bridle, or *vice versa* while it may also be easily converted into a good halter, and is adapted for use as a hoppel.

SLEIGH BRAKE.—David Collard, Hope, Idaho. A transverse brake shaft is journaled in bearings in the upper horizontal portion of the usual truss braces of the runners, this shaft being conveniently operated by a lever within easy reach of one in the sleigh, and the shaft carrying a gear wheel meshing with teeth on a nearly vertical bar, sliding in sockets, and the lower end of which forms the brake shoe. The construction is simple and the brake may be readily manipulated, while it may be attached to a sleigh in such a manner as not to weaken the runners.

CIGAR LIGHTER.—Franz Michl, New York City. This device consists of two tubes open at their ends and connected by an intervening plate, a cord or wick with attached chain being movable through one of the tubes, while in the other tube is a bottle having a stopper with a downwardly projecting needle. In the bottle is an alloy of sodium, potassium and zinc, and on touching a drawn-out end of the cord with the needle containing a small portion of the alloy the cord takes fire. The needle is replaced in the bottle and the cord drawn back into its tube to extinguish the flame, when the lighter may be returned to the pocket.

BUTTON EXHIBITOR.—Samuel T. Mosser, Abingdon, Ill. This device consists of a screen-covered cylinder, mounted to revolve in a case, a series of button-carrying brackets with hooks engaging the meshes of the cylinder to hold the brackets in place. The improvement is designed to afford a simple means to show to advantage a large quantity of goods, keeping them out of the dust and dirt, and holding them in such a way that any of the goods may be reached and removed when desired.

WASHING MACHINE.—John P. Hallsten and Charles J. Anderson, Rock Island, Ill. This is a double-acting machine in which rubbing boards are made to rub on both sides of the clothing at the same time, in the same manner as clothing is rubbed upon a washboard by hand, the work being more easily and rapidly done. The tube is formed with toothed cleats and reciprocating rubber boards, the upper board having on its upper side rollers upon which bears a spring-pressed bar. The rubbing boards are simultaneously moved in opposite directions by the operation of a lever, the clothes being rubbed between them.

WASH BOARD.—John C. Gearhart, Williamsport, Pa. This board has a removable and reversible rubbing plate, grooved or corrugated on its opposite faces, the main frame receiving laterally through or within it the marginal portions of the plate. An adjustable slide closes the slot in the side upright for the entry and removal of the plate.

CLOTHES LINE.—Jonathan W. Cadwell, Meriden, Conn. This is an improvement in clothes lines designed to extend from a window to an

outer support, providing a device which will permit the washed clothes to be secured on an auxiliary line within the house, and affording convenient means for the attachment of this auxiliary line to the main endless clothes line stretched upon supports from the window outwardly. The clothes may thus be transferred to the outer air for drying in a convenient and entirely safe manner.

VEST AND DRAWERS HOLDER.—Albert Lustig, Corsicana, Texas. This holder is made of a main strip of metal, having at one end a downwardly projecting portion with a clasp for connecting with the drawers, the strip also having fastening devices for connection with the vest, the strip having sufficient elasticity to hold the vest down to prevent wrinkling, and without forming a rigid, unyielding connection.

Designs.

DESIGN FOR A PAPER WEIGHT.—Lawrence J. Heffernan, New York City. The base of this device is shaped as the frustum of a prismatic pyramid, on which is an overhanging triangular tablet bearing a representation of a human head purporting to be that of Columbus, a ruching intervening the head and tablet.

BRIDLE BIT FRAME.—Wright W. Hall, New Windsor, Col. This frame has opposite slightly curved side plates, with a cross bar about the middle of their length, there being holes in the plates around the ends of the bar, while between the lower portions of the plates is a projecting curved round bar, and the lower ends of the plates have curved slots.

SPOON.—Edmund I. Richards, Brooklyn, N. Y. The end of the handle of this spoon is in the shape of a shield, within which is a large letter C, surrounding the letter E.

NOTE.—Copies of any of the above patents will be furnished by Munn & Co., for 25 cents each. Please send name of the patentee, title of invention, and date of this paper.

SCIENTIFIC AMERICAN
BUILDING EDITION.

OCTOBER NUMBER.—(No. 84.)

TABLE OF CONTENTS.

1. Elegant plate in colors, showing a handsome residence at Belle Haven Park, Greenwich, Conn., recently erected at a cost of \$18,000 complete. Floor plans and two perspective elevations. Messrs. Lamb & Rich, architects, New York.
2. Plate in colors showing an elegant residence at Montclair, N. J. Perspective view and floor plans. Cost \$7,000 complete. Mr. E. T. Hapgood, architect, New York. An excellent design.
3. A house at Montclair, N. J. Two perspective views and floor plans. Cost \$4,750 complete. E. T. Hapgood, architect, New York.
4. A Queen Anne cottage recently erected on Chester Hill, Mount Vernon, N. Y., at a cost of \$5,000. Floor plans, perspective elevation, etc.
5. A house for two families erected on Armory Hill at Springfield, Mass., at a cost of \$7,000 complete. Mr. F. R. Richmond, architect, Springfield, Mass. An excellent design. Floor plans and perspective.
6. A model dwelling at Holyoke, Mass. A unique design. Perspective elevation and floor plans.
7. A small cottage and separate summer kitchen. Perspective views and floor plan. Cost for both buildings, about \$1,600.
8. The parsonage at Montclair, N. J., built for the Congregational Church. Cost complete \$15,000. J. C. Cady & Co., architects, New York. Perspective view and floor plans.
9. A handsome residence at South Orange, N. J. Floor plans and perspective elevation.
10. A cottage at Fanwood, N. J., erected at a cost of \$5,166 complete. Perspective elevation and floor plans.
11. Portal of the church of Moret-sur-Loing, France.
12. Illustrations of two handsome English country houses.
13. Miscellaneous contents: The coming age of marble.—White brick.—How to keep out the heat in summer and to keep it in in the winter.—House moving.—Tempering tools.—Closet door fastenings.—A right-of-way may be built over.—Stanley plumbs and levels, illustrated.—Safety crane, illustrated.—An improved range and heater, illustrated.—Railway window sashes.—A great tunnel.—Inside sliding blinds, illustrated.—About floors.—A fine steel ceiling, illustrated.—An improved door hanger, illustrated.

The Scientific American Architects and Builders Edition is issued monthly. \$2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages; forming, practically, a large and splendid MAGAZINE OF ARCHITECTURE, richly adorned with elegant plates in colors and with fine engravings, illustrating the most interesting examples of Modern Architectural Construction and allied subjects.

The Fullness, Richness, Cheapness, and Convenience of this work have won for it the LARGEST CIRCULATION of any Architectural publication in the world. Sold by all newsdealers.

MUNN & CO., PUBLISHERS,
361 Broadway, New York.

© 1892 SCIENTIFIC AMERICAN, INC.

Press. See Cotton press. Printing press. 483,613
 Pressure gauge, duplex, F. H. Haskell. 483,792
 Printer's quoin, E. A. & A. G. Schmid. 483,792
 Printer's use, block for, E. B. Sheldon. 483,814
 Printing press, S. G. O. Sumner. 483,887
 Printing presses, electro-magnetic mechanism for operating, E. H. Kormeyer. 483,564
 Protector. See Coffin protector. 483,928
 Pruning implement, F. P. Kern. 483,588
 Pruning implement, W. D. Sunderlin. 483,588
 Puller. See Nail puller. 483,647
 Pulley, split, J. C. Piester. 483,647
 Pulp drainer, G. L. Jaeger. 483,847
 Pump, H. H. Cummings. 483,666
 Pump, M. M. Smith. 483,637
 Pump and dripper for barrels, combined, C. B. Alford. 483,757
 Puzzle, C. S. Ford. 483,912
 Puzzle, J. A. Sloan. 483,772
 Puzzle, J. W. Thorne. 483,820
 Pyroxyline, apparatus for the manufacture of transparent sheets of, E. N. Todd. 483,701
 Race course for horses, H. S. Butler. 483,600
 Rack. See Hay and stock rack. Hose rack. Pen and letter rack. 483,518
 Rail fastening, H. Alexy. 483,898
 Rail joint and chair, J. H. Campbell. 483,898
 Rail joint fastener, R. Morrell. 483,894
 Railway cable, J. B. Mahaffey. 483,905
 Railway chair, W. Wharton. 483,592
 Railway, electric, W. G. Murphy, Jr. 483,856
 Railway grip, cable, C. Vogel. 483,775
 Railway grippable, Vogel & McIntosh. 483,774
 Railway or farm gate, automatic, J. R. Benson. 483,890
 Railway rail fastener, R. Morrell. 483,855
 Railway rails, combined foot and brace for, V. Angerer. 483,889
 Railway rails, combined foot and brace for, E. Samuel. 483,873
 Railway signal case, L. A. Boyd. 483,528
 Railway switch, J. N. Strong. 483,818
 Railway tie, metal, S. H. Wilson. 483,821
 Railway tie, metallic, R. Morrell. 483,853
 Railway tie, metallic, B. F. & M. F. Sparr. 483,773
 Railways, closed conduits for electric, W. G. Creighton. 483,761
 Rake. See Hay rake. 483,659
 Record of certain merchandise in retail establishments, means for keeping stock, D. H. Stern. 483,659
 Recorder. See Time recorder. 483,907
 Reel. See Wire reel. 483,907
 Reel, A. Dobson. 483,876
 Refrigerating apparatus, Stacey & Lightfoot. 483,552
 Refrigerator and fruit car, combined, H. C. Goodell. 483,551
 Refrigerator car, ventilated, H. C. Goodell. 483,551
 Register. See Cash register. 483,899
 Rice hulling machine, E. L. Cantwell. 483,899
 Rice, etc., polishing, G. B. Prochaska. 483,598
 Rivet setting machine, Bray & Pope. 483,901
 Rock drilling machinery, A. E. Chodzko. 483,896
 Rod coupling, Buess & Cowling. 483,896
 Roller. See Shade roller. 483,896
 Roller mill feed, H. R. Shaw. 483,896
 Rolling mill, G. W. Jones. 483,929
 Rolling mill, P. L. Kimberly. 483,929
 Roof, L. H. Montross. 483,966
 Root cutter, D. Maxwell. 483,726
 Rotary steam engine, F. A. Small. 483,530
 Roundabout, J. L. Buford. 483,671
 Routing machine, W. Greaves. 483,573
 Roving frame, Morgan & McMillan. 483,769
 Sad iron, J. Sabold. 483,878
 Sad iron heater, F. R. Sutton. 483,754
 Saddle pad, harness, S. Whitman. 483,886
 Safety pin, hook and eye, E. M. Wright. 483,948
 Sanitary seal for covers of toilet vessels, C. Smart. 483,837
 Sash fastener, A. S. Fisher. 483,765
 Sash, reversible window, G. Hoersch. 483,971
 Saw attachment, H. C. Webb. 483,765
 Saw set, H. B. Smith. 483,765
 Sawing machine, drag, Kirksey & Bowden. 483,630
 Scale, coin-operated weighing, G. G. Merry. 483,787
 Scale, weighing and recording, R. McFarlane. 483,675
 Scarf clasp, J. J. Halahan. 483,783
 Screen. See Window screen. 483,867
 Seal lock, J. B. Price. 483,867
 Seal. See Spring seal. 483,867
 Sewing machine, feeding mechanism, B. F. Belows. 483,800
 Shade roller, spring, E. F. Hartshorn. 483,553
 Shade supporter, window, S. T. Stuver. 483,796
 Shaft attachment, vehicle, F. M. Merrick. 483,568
 Shaving case, H. T. Peters. 483,579
 Shears. See Animal shears. 483,834
 Shelf bracket, T. Corscaden. 483,963
 Shoe holder, E. Leger. 483,963
 Silver ores, smelting complex, C. James. 483,962
 Sliding gate, double suspended, P. E. Jensen. 483,614
 Sole, prouts & Ball. 483,580
 Sole staining machine, F. L. Richardson. 483,623
 Sowing machine, E. G. Thoren. 483,846
 Speed measure, O. Knapp. 483,906
 Spinning mule, P. N. Dexter, Jr. 483,918
 Spittoon for railway cars, E. L. Harris. 483,576
 Spool boring machine, J. M. Parker. 483,699
 Spring. See Cheek spring. 483,521
 Spring seat, S. G. Scarratt. 483,521
 Square, tailor's measuring, P. N. Arvidson. 483,905
 Steam boiler, J. D. Hulings. 483,544
 Stereotype plate and base, J. R. Cummings. 483,716
 Stereotype, automatic regulating, C. G. Meyer. 483,562
 Storage battery, E. R. Knowles. 483,610
 Store service apparatus, R. Gornall. 483,591
 Stove, lamp, S. L. Walker. 483,880
 Stove mat, W. J. Turpin. 483,932
 Stove plate, vapor, F. J. Little. 483,702
 Street sweeper, A. B. Vandemark. 483,593
 Sunshade, vehicle, V. L. Luc. 483,593
 Supporter. See Box supporter. Invalid supporter. Shade supporter. 483,900
 Surgical chair, F. E. Case. 483,615
 Suspending device, J. I. Johnson. 483,615
 Switch. See Electric switch. Electric snap switch. 483,747
 Tack driving machine, E. Patten. 483,734
 Tank. See Lampfilling tank. Weighing oil tank. 483,768
 Tanning vat, leather, B. P. Bradford. 483,718
 Telegraph receiver, C. A. Rolfe. 483,718
 Telephone receiver, F. Gross. 483,887
 Tensioning machine marking attachment, C. J. Zimmerman. 483,662
 Thermometer scale, S. E. Ward. 483,629
 Tie. See Railway tie. 483,767
 Time recorder, workman's, A. L. Jaynes. 483,629
 Time recording mechanism, D. E. Pursell. 483,629
 Time piece dial, G. Reiss. 483,567
 Tire, pneumatic, T. W. Robertson. 483,571
 Tobacco filler, W. P. & O. Marshall. 483,865
 Tongs, flooring and siding, G. W. Miller. 483,865
 Tool handle, Potter & Danerfeld. 483,727
 Toy animal figure, C. M. Smith. 483,597
 Transom lifter, C. L. Boehme. 483,961
 Trap for sinks, etc., D. A. Horgan. 483,683
 Trolley catcher, J. J. Hoppes. 483,969
 Trough. See Feed trough. 483,790
 Tug hook, harness, J. Green. 483,693
 Turning machine, wood, Bennett & Haidacher. 483,693
 Valve, automatic regulating, J. M. Foster. 483,635
 Valve check, E. W. Craine. 483,635
 Valve check, S. F. Prince, Jr. 483,725
 Valve controller, hygienic, C. W. Rogers. 483,885
 Vapor burner, J. S. Wood. 483,717
 Vat. See Tanning vat. 483,605
 Vehicle running gear, H. T. Goodrich. 483,559
 Veil pin, G. H. Fien. 483,875
 Velocipede saddle, J. A. Hunt. 483,650
 Velocipede saddle, F. M. Slocum. 483,875
 Ventilator. See Air ventilator. 483,650
 Ventilator, Gross & Beck. 483,575
 Vessel closure, J. B. McNabb. 483,770
 Vessels, apparatus for ejecting ashes from, H. See. 483,627
 Vine cutter, S. H. Francis. 483,858
 Vine holder, J. L. McGarrell. 483,897
 Violin, D. F. Burgner. 483,590
 Wadding from cellulose and cotton, process of and machine for manufacturing, C. Waibel. 483,927
 Wall, floor, or roof of buildings, A. J. Judge. 483,786
 Wash board breast rest, O. T. & J. H. Lapham. 483,526
 Washstand water receptacle, N. O. Bond. 483,547
 Washing machine, W. F. Elkins. 483,721
 Washing machine, F. D. Hubert. 483,723
 Washing machine, J. A. Mengel. 483,861
 Washing machine, C. Osborn. 483,634
 Washing powder, E. F. O'Neal. 483,949
 Watch charm, Smith & Grapewine. 483,960
 Watchmaker's depth and adjusting tool, G. W. Harris. 483,961
 Water meter, H. B. Williams. 483,636
 Weighing apparatus, automatic, M. E. Reiser. 483,909
 Weighing machine, grain, Droste & Bruns. 483,909
 Weighing oil tank, Bachelder & Lovejoy (r). 11,274
 Well drilling machine, G. Zink. 483,756
 Wheel. See Metal wheel. 483,604
 Whiffletree, J. J. Edgar. 483,850
 Wick carrier, J. C. Miller. 483,520
 Windmill towers, etc., adjustable brace for, M. J. Althouse. 483,608
 Window chair, E. B. Gildersleeve. 483,968
 Window frame pocket, F. V. Phillips. 483,799
 Window screen, W. E. Pierce. 483,968
 Wire netting machine, B. Scaries. 483,968

Wire reel, J. W. Buchanan. 483,880
 Wood working machines, feed roller for, J. Davis. 483,711
 Wrench. See Pipe wrench. 483,803
 Wrench, L. I. Fdk et al. 483,803
 Zinc furnace, C. O. Sumner. 483,887
 Zinc, reducing, C. James. 483,652

DESIGNS.

Badge, A. T. Hatch. 21,875
 Corset, D. H. Warner. 21,883
 Cuff holder stand, H. C. Frank. 21,876
 Game board, M. E. Cameron. 21,880
 Organ case top, O. E. Brandt. 21,881
 Spoon, A. Ludwig. 21,879
 Table vessel, C. V. Helmschmied. 21,878
 Vase, etc., S. Starkey. 21,877

TRADE MARKS.

Antipretic, G. E. Dixon. 21,841
 Bath tubs, G. Booth. 21,806
 Boots and shoes, Smith Bros. 21,815
 Boots and shoes, T. A. Wicher & Co. 21,838
 Buckwheat, kraham flour, cornmeal, rolled oats, and similar manufactured cereals, F. L. Thornton. 21,823
 Buggies, top, C. H. Palmer, Jr. 21,837
 Capsules for medicinal use, H. H. Blood. 21,851
 Cements, hydraulic and other, Eisner & Mendelsohn Co. 21,853
 Chemical products, F. von Heyden. 21,843
 Cigar, Foster-Hilson Company. 21,843
 Corsets, ladies' French, Syndicate Trading Company. 21,816
 Dyes or colors, Farberer Glauchau, vormals O. Seyfert. 21,842
 Flour, wheat, W. H. Stokes. 21,817
 Gas and gasoline engines, Palmer & Rey. 21,834
 Gas, liquefied carbonic acid, Truslow & Co. 21,848
 Hats, Volk Hat Company. 21,825
 Hosiery, J. Black & Sons. 21,831
 Ice chests, coolers, and refrigerators, Challenge Corn Planter Company. 21,810
 Medicaments, pills, and salts, A. Loring. 21,845
 Medicament soap, Cincinnati Soap Co. 21,832
 Medicine for fowls, Orlando Medicine Company. 21,833
 Oranges, D. Tillson. 21,824
 Plowshares, L. A. Weyburn Company. 21,826
 Poultry and eggs, M. Plowart. 21,854
 Preservative, chemical, O. Hann & Bro. 21,854
 Remedies for external use, S. L. Willard. 21,849
 Remedy for diseases of the kidneys and genital organs, J. C. Auchampaugh. 21,850
 Remedy for the piles, W. T. Strong. 21,814
 Remedy for the toothache, R. Arduvini. 21,829
 Sarsaparilla compound, H. L. & J. E. Woodcock. 21,827
 Sash locks and fasteners, W. A. Bomar. 21,840
 Sheep dip or cattle wash, F. D. Banning. 21,830
 Shirts, collars, cuffs, and blouses, C. H. McClellan. 21,821
 Silver polish in the form of powder and soap. Electro Silicon Company. 21,820
 Soap, W. H. Hall. 21,812
 Soap, laundry, J. W. & T. W. Alexander. 21,839
 Soap, laundry, Reade Manufacturing Company. 21,813
 Lye, powdered, Champion Chemical Works. 21,809
 Tea, Paxton & Gallagher. 21,847
 Tobacco and cigars, chewing and smoking, G. A. Neff et al. 21,855
 Toy, C. A. Boyd. 21,852
 Type writing machine, Wyckoff, Seamans & Benedict. 21,819
 Velocipedes and parts thereof and wheels for use in light vehicles, Ames & Frost Company. 21,826
 Whips, Pomeroy & Van Deusen. 21,844
 Whisky, S. C. Boehm & Co. 21,807
 Whisky, rum, gin, cordials, and California wines and brandy, Delafeld, McGovern & Co. 21,811

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1883, will be furnished from this office for 25 cents. In ordering please state the name and number of the patent desired, and remit to Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list, provided they are simple, at a cost of \$40 each. If complicated the cost will be a little more. For full instructions address Munn & Co., 361 Broadway, New York. (Other foreign patents may also be obtained.)

Advertisements.

Inside Page, each insertion - - 75 cents a line
 Back Page, each insertion - - - \$1.00 a line

The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may be advertised at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at Publication Office as early as Thursday morning to appear in the following week's issue.

KEUFFEL & ESSER CO.
 NEW YORK
 AND CHICAGO.
 Patent Triangular and flat
 Paragon Scales, the best and
 most convenient. Boxwood
 scales. Paper scales. Special
 scales to order. Scales in sets

AGENTS WANTED

In every County throughout the United States to handle our fast-selling specialties; will sell in every home. Send two cent stamp for illustrated catalogue, terms, etc.

ELECTRO-NOVELTY CO.
 5-10 AMORY AVENUE, ROXBURY, MASS.
 N.B.—For description of Toy Motors manufactured by us, see July 23d issue Scientific American.

LA
 \$85
 Foot Lathe
 Swings
 9x25 in.
 Screw Cutting
 Automatic
 Feed, etc.

Seneca Falls Mfg. Co. 569 Water St., Seneca Falls, N.Y.

The Sebastian-May Co

Improved Screw Cutting

Foot & Power LATHES

Drill Presses, Chucks, Drills, Dies, and Machinists' and Amateurs' Outfits. *Lathe on trial.* Catalogues mailed on application.

165 to 167 Highland Ave., SIDNEY, OHIO.

Improved Screw Cutting

Foot and Power LATHES

Drill Presses, Shapers, Band, Circular, and Scroll Saws. Machinists' Tools and Supplies. Lathes on trial. *Catalogue mailed on application.*

SEBASTIAN LATHE COMPANY,
 120 and 122 Culvert Street, Cincinnati, O.

BEATTY Piano. Organ. \$23 up. Want agents

Cat'g free. Dan'f. Beatty, Wash'ton, N.J.

OIL WELL SUPPLY CO.
 91 & 92 WATER STREET,
 PITTSBURG, PA.
 Manufacturers of everything needed for
ARTESIAN WELLS
 for either Gas, Oil, Water, or Mineral
 Tests, Boilers, Engines, Pipe,
 Cordage, Drilling Tools, etc.
 Illustrated catalogue, price
 lists and discount sheets
 on request.

WELL DRILLING MACHINERY,
 MANUFACTURED BY
WILLIAMS BROTHERS,
 ITHACA, N. Y.,
 Mounted and on Sills, for
 deep or shallow wells,
 with steam or horse
 power.
 Send for
 Catalogue.
 ADDRESS
 Williams Brothers
 ITHACA, N. Y.

LIGHTNING WELL-SINKING
 MACHINERY MANUFACTURERS.
 Hydraulic, Jetting, Revolving, Artesian,
 Diamond Prospecting Tools, Engines, Boilers,
 Wind Mills, Pumps, etc.
 Engravings, Earth's Strata, Determination
 quality water; mailed, 25c.
 The American Well Works,
 Aurora, Ill.
 11 & 13 S. Canal
 St.,
 Dallas, Texas

FOR RENT, WATER POWER.—Day use of 250 h. p. (night power used for Electric Light plant). Good railroad facilities. Town of 6,000 population. Address Riverside Water Company, Riverside, California.

New Full Mounted Lightning Screw Plate.
 Send for Catalogue.

WILEY & RUSSELL MFG. CO., Greenfield, Mass., U.S.A.

ALUMINUM: ITS USES AND APPLICATIONS.

A valuable and interesting article by G. L. Addenbrooke. Contained in **SCIENTIFIC AMERICAN** SUPPLEMENT No. 859. Price 10 cents. To be had at this office and from all newsdealers.

Industrial, Manufacturing, and Uncurrent
SECURITIES DEALT IN.
WORDEN & FANSHAW,
 9 WALL ST., NEW YORK.

MALLEABLE AND FINE GRAY IRON ALSO ST. & F. CASTINGS FROM SPECIAL PATTERNS.
THOMAS DEVLIN & CO.
 LEHIGH AVE. & AMERICAN ST. PHILA.

SPECIAL NOTICE!
 Two handsome photo-engraved display sheets entitled, "Recent Improvements in Air Compressors," "Recent Improvements in Rock Drills," mailed free to any one who will cut out this advertisement and mail it to us with his name and address.
INGERSOLL-SERGEANT DRILL CO.
 No. 10 Park Place, New York, U.S.A.

ROCK DRILLS
AIR COMPRESSORS &
GENERAL MACHINERY FOR
MINING, TUNNELING,
QUARRY & RAILROAD WORK
RAND DRILL CO. 23 PARK PLACE NEW YORK

GAS and GASOLINE ENGINES
STATIONARY and PORTABLE. All Sizes.
Dwarfs in Size, but
Giants in Strength.
 Expense one cent an hour per horse power and requires but little attention to run them.
Every Engine
 Guaranteed. Full particulars free by mail. Mention this paper.
VAN DUZEN
GAS & GASOLINE ENGINE CO. Cincinnati, O.

Steel Type for Writing Machines,
 J. D. MALLONEE, MTR, STOCKTON, N. Y.

WOODEN TANKS
 LARGE WATER TANKS
 PLANS & A SPECIALTY
 SPECIFICATIONS FURNISHED
 FOR FOUNDATIONS & TOWERS
 No. 217 E. MAIN ST. LOUISVILLE KY.
WECALDWELL CO.

CATALOGUES FREE TO ANY ADDRESS
GEARS AND PARTS OF
MODELS
GOODNOW & WIGHTMAN
 BOSTON

OIL-LIME-ELECTRIC
2nd MAGIC
 LANTERNS,
 STEREOSCOPES
 AND VIEWS.
 Large Catalogue Free.
 16 Beekman Street, N. Y. City.
J. B. COIT & CO. 189 La Salle Street, Chicago, Ill.

NEW YORK TRADE SCHOOLS.—Description of the New York Trade Schools which were established nine years ago for the purpose of giving instructions to young men in certain trades, and to enable young men already in such trades to improve themselves. With 10 illustrations. Contained in **SCIENTIFIC AMERICAN** SUPPLEMENT, No. 781. Price 10 cents. To be had at this office and from all newsdealers.

TRENTON IRON CO.
 TRENTON
 N. J.
STEEL MUSIC WIRE
 EQUAL TO THE BEST IMPORTED
 NEW YORK
COOPER, HEWITT & CO.

INVENTORS' IDEAS put into practical working shape by
MILLIKEN & D'AMOUR,
 COR. JOHN AND DUTCH STREETS, NEW YORK CITY.
 Machinists, Pattern and Model Makers.

WATER WHEELS
JAMES LEFFEL & CO.,
 SPRINGFIELD, OHIO, U.S.A.
 Send for our fine large PAMPHLET.

NOW READY!
A NEW AND VALUABLE BOOK.

THE SCIENTIFIC AMERICAN
CYCLOPEDIA
 OF
 RECEIPTS,
 NOTES AND
 QUERIES.

12,000 Receipts. 680 Pages. Price \$5.

This splendid work contains a careful compilation of the most useful Receipts and Replies given in the Notes and Queries of correspondents as published in the **Scientific American** during the past fifty years; together with many valuable and important additions.

Over Twelve Thousand selected receipts are here collected; nearly every branch of the useful arts being represented. It is by far the most comprehensive volume of the kind ever placed before the public.

The work may be regarded as the product of the studies and practical experience of the ablest chemists and workers in all parts of the world; the information given being of the highest value, arranged and condensed in concise form convenient for ready use.

Almost every inquiry that can be thought of, relating to formulae used in the various manufacturing industries, will here be found answered. Instructions for working many different processes in the arts are given.

It is impossible within the limits of a prospectus to give more than an outline of a few features of so extensive a work.

Under the head of Paper we have nearly 250 receipts, embracing how to make papier mache; how to make paper water proof and fire proof; how to make sandpaper, emery paper, tracing paper, transfer paper, carbon paper, parchment paper, colored papers, razor strap paper, paper for doing up cutlery, silverware; how to make luminous paper, photograph papers, etc.

Under the head of Inks we have nearly 450 receipts, including the finest and best writing inks of all colors, drawing inks, luminous inks, invisible inks, gold, silver and bronze inks, white inks; directions for removal of inks; restoration of faded inks, etc.

Under the head of Alloys over 700 receipts are given, covering a vast amount of valuable information.

Of Cements we have some 600 receipts, which include almost every known adhesive preparation, and the modes of use.

How to make Rubber Stamps forms the subject of a most valuable practical article, in which the complete process is described in such clear and explicit terms that any intelligent person may readily learn the art.

For Lacquers there are 120 receipts; Electro-Metallurgy, 125 receipts; Bronzing, 127 receipts; Photography and Microscopy are represented by 600 receipts.

Under the head of Etching there are 55 receipts, embracing practical directions for the production of engravings and printing plates of drawings.

Paints, Pigments and Varnishes furnish over 800 receipts, and include everything worth knowing on those subjects.

Under the head of Cleansing over 500 receipts are given, the scope being very broad, embracing the removal of spots and stains from all sorts of objects and materials, bleaching of fabrics, cleaning furniture, clothing, glass, leather, metals, and the restoration and preservation of all kinds of objects and materials.

In Cosmetics and Perfumery some 500 receipts are given.

Soaps have nearly 300 receipts.

Those who are engaged in any branch of industry probably will find in this book much that is of practical value in their respective callings.

Those who are in search of independent business or employment, relating to the home manufacture of sample articles, will find in it hundreds of most excellent suggestions.

Send for descriptive circular.

MUNN & CO., Publishers,

SCIENTIFIC AMERICAN OFFICE,

361 Broadway, New York.

Edwards' Works on the Steam Engine

The American Marine Engineer, Theoretical and Practical; with Examples of the Latest and Most Approved Marine Practice. For the Use of Marine Engineers and Students. By Emory Edwards, Marine Engineer. Illustrated by 85 engravings. 12mo. 435 pages. \$2.50

Edwards' 600 Examination Questions and Answers, for Engineers and Firemen (Stationary and Marine) who desire to obtain a U. S. Government or State License. By Emory Edwards. Full bound in pocket book form, leather. 130 pages. \$1.50

The American Steam Engineer, Theoretical and Practical; with Examples of the Latest and Most Approved American Practice in the Design and Construction of Steam Engines and Boilers of Every Description. For the Use of Engineers, Machinists, Boiler Makers, and Students. By Emory Edwards, M.E. Illustrated by 77 engravings. 12mo. 419 pages. \$2.50

Modern American Marine Engines, Boilers, and Screw Propellers. Their Design and Construction. Showing the Present Practice of the most Eminent Engineers and Marine Engine Builders in the United States. By Emory Edwards. Illustrated by 30 large and elaborate plates. 4to. \$5.00

The Practical Steam Engineer's Guide in the Design, Construction, and Management of American Stationary, Portable, and Steam Fire Engines, Steam Pumps, Boilers, Injectors, Governors, Indicators, Pistons, and Rings, Safety Valves and Steam Gauges. For the Use of Engineers, Firemen, and Steam Users. Illustrated by 119 engravings. 420 pages, 12mo. \$2.50

A Catechism of the Marine Steam Engine. For the Use of Engineers, Firemen, and Mechanics. A Practical Work for Practical Men. Illustrated by 63 engravings, including examples of the most modern engines. Fifth edition, thoroughly revised, with much new matter. 12mo, 414 pages. \$2.00

Modern American Locomotive Engines. Their Design, Construction, and Management. Illustrated by 78 engravings. 12mo, 383 pages. \$2.00

The above or any of our Books sent by mail, free of postage, at the publication prices, to any address in the world.

Illustrated circulars, showing full tables of contents of all of the above valuable books, will be sent free to any one in any part of the world who will send his address.

Our new and revised Catalogue of Practical and Scientific Books, 88 pages, 8vo., as well as our other catalogues and circulars, the whole covering every branch of Science applied to the Arts, sent free and free of postage to any one in any part of the world who will furnish his address.

HENRY CAREY BAIRD & CO.

INDUSTRIAL PUBLISHERS, BOOKSELLERS & IMPORTERS

810 Walnut St., Philadelphia, Pa., U. S. A.

THE RAILROAD ISSUE

THE INDEPENDENT.

CONTENTS. OCTOBER, 6, 1892.

THE NIGHT EXPRESS—POEM. Bliss Carman.
THE PUBLIC AND THE RAILWAYS.
The Hon. Shelby M. Cullom, U. S. Senator from Illinois.

ENGLISH AND AMERICAN RAILWAYS.
W. M. Acworth, Esq., London.

A BUREAU OF RAILWAY STATISTICS AND ACCOUNTS.
Henry C. Adams, Esq., Statistician of the Inter-State Commerce Commission.

HIGH SPEED RAILROAD TRAVEL.
Theodore Voorhees, Esq., General Superintendent, New York Central Railroad.

ARBITRATION AS RELATED TO LABOR.
Col. Adna C. Walker, President of the Western Traffic Association.

THE FUTURE OF THE INTER-STATE COMMERCE COMMISSION.
Walter D. Dabney, of the Inter-State Commerce Commission.

UNITY OF RAILWAYS AND RAILWAY INTERESTS.
Hon. A. Schoenmaker, ex-Inter-State Commerce Commissioner.

LONG vs. SHORT HAULS.
Gen. E. P. Alexander.

THE TREATMENT OF RAILROAD EMPLOYEES.
B. B. Adams, Jr., of "The Railroad Gazette."

STATE CONTROL OF RAILROAD BUILDING.
Prof. Frederick Clark, Ph.D., of Leland Stanford University.

In addition, contributed articles upon a variety of subjects, together with the usual Departments, 44 pages in all.

Single copies, 10 Cents. Yearly subscription, \$3.00

THE INDEPENDENT.

114 Nassau Street, New York.

RAINMAKERS IN THE UNITED STATES.—A full account of the operations in the production of rain recently carried out under federal appropriations in Texas. One illustration. Artificial rain making. By Prof. E. J. Houston. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 824. Price 10 cents. To be had at this office and from all newsdealers

ALANSON CARY

STEEL SPRINGS

OF EVERY DESCRIPTION

240 & 242 W 29TH ST. NEW-YORK

WHAT ELECTRICITY IS—BY W. W. Jacques. An interesting discussion of the subject, illustrated with some new experiments. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 857. Price 10 cents. To be had at this office and from all newsdealers.

THE BEST LOOSE PULLEY OILER

IN THE WORLD.

VANDUZEN PAT. L. PUL. OILER

Keeps Pulley oiled 3 to 4 weeks with one filling. Cost 25, 30, 40, 50, 65 and 85 cents each. Send Price and TRY ONE.

State diameter and speed of Pulley. Will send Catalogue free. Mention this paper.

The VANDUZEN & TIFT CO. Cincinnati, O., U.S.A.

DEAFNESS & HEAD NOISES CURED


by Peck's Invisible Tubular Ear Cautions. Whispers heard. Successful when all remedies fail. Sold only by F. H. SOX, 868 Broadway, N.Y. Write for book of proofs FREE

TO BUSINESS MEN

The value of the SCIENTIFIC AMERICAN as an advertising medium cannot be overestimated. Its circulation is many times greater than that of any similar journal now published. It goes into all the States and Territories, and is read in all the principal libraries and reading rooms of the world. A business man wants something more than to see his advertisement in a printed newspaper. He wants circulation. This he has when he advertises in the SCIENTIFIC AMERICAN. And do not let the advertising agent influence you to substitute some other paper for the SCIENTIFIC AMERICAN, when selecting a list of publications in which you decide it is for your interest to advertise. This is frequently done for the reason that the agent gets a larger commission from the papers having a small circulation than is allowed on the SCIENTIFIC AMERICAN.

For rates see top of first column of this page or address MUNN & CO., Publishers.

361 Broadway, New York.



ROCK BREAKERS AND ORE CRUSHERS

We manufacture and supply at short notice and lowest rates, Stone and Ore Crushers containing the improved Patent described in Letters Patent No. 1,188, together with NEW AND VALUABLE IMPROVEMENTS, for which Letters Patent were granted May 11 and July 20, 1880, to Mr. S. L. Marsden. All Crushers supplied by us are constructed under these patents.

FARRELL FOUNDRY & MACHINE CO., Manufacturers, ANSONIA, CONN.

COPELAND & BACON, Agents, NEW YORK and CHICAGO.

CHUCKS.

Catalogue No. 12, just issued with over 40 new illustrations sent free. Address,

The Cushman Chuck Co., Hartford, Conn.

SCIENTIFIC AMERICAN SUPPLEMENT.

Any desired back number of the SCIENTIFIC AMERICAN SUPPLEMENT can be had at this office for 10 cents. Also to be had of newsdealers in all parts of the country.

MY WIFE SAYS SHE CANNOT SEE HOW YOU DO IT FOR THE ONLY \$12 Sewing Machine; perfect working machine, finely finished, adapted to light and heavy work, with a complete set of the latest improved attachments free. Each machine guaranteed for 5 years. Buy direct from our factory, and save dealer and agents profit. Send for FREE CATALOGUE. OXFORD MFG. COMPANY, DEPT. D, 18 CHICAGO, ILL.

"2 MONTHS ON TRIAL" FOR 10c.

An illustrated monthly journal for the amateur, experimenter and public. BUBIER PUB. CO., LYNN, MASS.

"ECONOMY IS WEALTH."

Canvassers wanted to sell the New Model Mail Typewriter. Why will people buy a \$100 machine when \$30 will purchase a better one? Send for illustrated catalogue and terms to County Agents.

Address N. TYPEWRITER CO., 611 Washington Street, Boston, Mass. Mention Scientific American.

THE ZELL IMPROVED SAFETY BOILER. MANUFACTURED BY THE CAMPBELL & ZELL CO. IRON, BRASS, AND STEEL. ESSEX & BURKE STREETS, BALTIMORE, MD.

FREE SITES TO SUBSTANTIAL MANUFACTURING ENTERPRISES

In the rapidly growing towns of Virginia and West Virginia, possessing CHEAP IRON, CHEAP LUMBER, CHEAP FUEL, and RAILROAD FACILITIES, address J. H. DINGEE, 833 Walnut Street, Philadelphia, Pa., President and General Manager of numerous Land Companies situated along the lines of the Norfolk & Western Railroad.

Foot Lathe. SCREW CUTTING. ADDRESS FOR \$40 CIRCULAR. NARRAGANSETT MACH. CO. BOX 1008 PROVIDENCE, R.I.

The Belknap Little Giant Water Motor

Best Water Motor, most powerful and efficient machine on the market. Electric Motors and Dynamos. Combined Water Motors and Dynamos. Cyclone Coffee Mills for Grocers' use. Combined Motor and Mill in one case, run by water or electricity. Write for Circulars. BELKNAP MOTOR CO., 23 Plum St., Portland, Maine U. S. A.

Astronomical Telescopes

of superior defining power, EYE PIECES, etc. Manufactured by W. & D. MOGEY, 418 West 27th Street, New York. Send for catalogue.

"THE SINTZ" GAS AND GASOLINE ENGINES

Stationary and Marine. Makes its own supply of gas from gasoline, and at less expense than any other engine. No boiler, coal, or fireman required. Runs with either manufactured or natural gas. Specially adapted for small boats and launches and electric light work. Circulars free. Mention this paper. CLARK SINTZ, MFR., Springfield, Ohio.

OUR MAGIC LANTERNS. WITH OIL LAMPS HAVE NO EQUAL. VIEWS OF ALL SUBJECTS. LOWEST PRICES GUARANTEED. L. MANASSE 88 MADISON ST. CHICAGO ILL.

BOOKS.

Our entirely new 116 page Catalogue of Scientific and Technical Books, both American and Foreign, just issued, containing a record of nearly 3,500 books, and embracing more than 300 different subjects, arranged under a new plan with cross references and author's index, will be mailed free to any address in the world on application. Address

MUNN & CO.,

Publishers "Scientific American,"

No. 361 BROADWAY, NEW YORK.

GATES ROCK & ORE BREAKER

Capacity up to 200 tons per hour.

Has produced more ballast, road metal, and broken more ore than all other Breakers combined.

Builders of High Grade Mining Machinery. Send for Catalogues.

GATES IRON WORKS, 50 CSo. Clinton St., Chicago

136 C. Liberty Street, New York, 237 C. Franklin St., Boston, Mass

C. E. HORN & CO.

Manufacturers and Jobbers of

ELECTRIC BELLS

63 SO. CANAL ST. Chicago, Ill. U. S. A.

The cheapest, simplest and most efficient bell manufactured.

Do you want our illustrated price list "H"?

HOW TO MAKE A STORAGE BATTERY.

By G. M. Hopkins. Directions for making a Planté battery and for charging the same. With 4 illustrations. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 845. Price 10 cents. To be had at this office and from all newsdealers.

BICYCLES ON EASY PAYMENTS

No extra charge. All makes new or 2d hand. Lowest price guaranteed. Largest stock and oldest dealers in U. S. Catalogue free. Agents wanted. Rouse, Hazard & Co., 16 St., Peoria, Ill.

A Great Advertising Medium.

The Architects and Builders Edition of the Scientific American. (Established 1885.)

This superb architectural work has by far the largest circulation of any periodical of its class. It goes directly into the hands of those who have the ordering of the great bulk of Building Materials and Appliances, namely, the Architects, Builders, Constructing and Sanitary Engineers, Contractors, and House Owners.

The Building Edition of the SCIENTIFIC AMERICAN is unquestionably the very best advertising medium for manufacturers and dealers in Building Materials, Carpenters' Tools, Woodworking Machinery, Heating, Ventilating, Plumbing and Sanitary Appliances, Roofing, Architectural Wood and Metal Work, Builders' Hardware, Doors, Sash, Blinds, Paints, and in fact all goods which enter into or are used in the construction and maintenance of Buildings or works of any kind.

The rates for advertising are moderate. For terms address MUNN & CO. Publishers, 361 Broadway, N. Y.

STEEL TYPE FOR TYPEWRITERS

Stencils, Steel Stamps, Rubber and Metal Type Wheels, Dies, etc. Model and Experimental Work. Small Machinery, Novelties, etc., manufactured by special contract. New York Stencil Wks. 100 Nassau St., N. Y.

THE SIMPLEX TYPEWRITER

to do as good work as any high priced machine. Specially adapted for use in private correspondence. Sent by mail or express prepaid on receipt of \$2.70. See Sci. Am., Oct. 1, p. 211. Address Simplex Typewriter Co., 39 Great Jones Street, New York.

TO PATENTEES.

Send \$1.00 for Robert Grimshaw's "TIPS TO INVENTORS." Valuable information as to what inventions are most needed and asked for, and how to develop ideas and dispose of Patents. Practical Publishing Co., 21 PARK ROW, N. Y.

The Shimer Cutter Heads

45,000 SOLD. To work Car Siding, Flooring, Ceiling and Ship Lap, to Mould Doors, Sash and Blinds. Cope Heads to match. Sam'l J. Shimer & Sons, Centre St., Milton, Pa.

DO YOU WANT TO Speculate? Make Money? Others Have Got Rich, Why Not You?

Write for Particulars. FREE. JOSEPH H. ALLEN, TREAS., 244 Washington St., Boston, Mass.

High Grade MECHANICAL and INSTRUMENT WORK

(Scientific, Precision, Philosophical and Electrical) WORK of every description, general or special, accurately, carefully, neatly and skillfully made in quantities desired, from drawings furnished us or from our own designs. Light and fine EXPERIMENTAL CLOCK, GEAR and MODEL WORK, MECHANICAL MOVEMENTS, etc., in Metal or Wood. Please write for terms. American Instrument Works, P. O. Box 1940, Boston, Mass.

ARTESIAN

Wells, Oil and Gas Wells, drilled by contract to any depth, from 50 to 300 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 1,000 feet. Write us stating exactly what is required and send for illustrated catalogue. Address

PIERCE ARTESIAN & OIL WELL SUPPLY CO., 80 BEAVER STREET, NEW YORK.

PROPOSALS.

UNITED STATES ENGINEER OFFICE, NO. 73 Fourth Street, Portland, Oregon, September 15, 1892. Sealed proposals, in duplicate, will be received at this office until 2 o'clock p. m., standard time, November 15, 1892, and then publicly opened, for furnishing all the material and labor necessary to complete the present project for improving canal at the cascades of the Columbia River, Oregon. Preference will be given to materials of domestic production or manufacture, conditions of quality and price (import duties included), being equal. Attention is invited to Acts of Congress, approved February 26, 1885, and February 28, 1887, vol. 23, page 332, and vol. 23, page 414, Statutes at Large. The Government reserves the right to reject any and all proposals, also to waive any informalities. Specifications, blank forms, and all available information will be furnished on application to this office. Persons intending to submit proposals must visit the locality of the works. THOS. H. HANDBURY, Major, Corps of Engineers, U. S. A.

IMPROVED CHARTER GAS ENGINES. USING GASOLINE, COAL GAS, ALCOHOL, PRODUCER GAS. RELIABLE, NO DELICATE PARTS, ECONOMICAL, SIMPLE. H.W. CALDWELL & SON, WASHINGTON & UNION STS. CHICAGO, ILLS.

CLARK'S WOOL WASHERS.

WARP DYEING AND SIZING MACHINES. PATENT RUBBER COVERED SQUEEZE ROLLS.

POWER WRINGERS FOR HOSIERY AND VARN DYEING.

DRYING AND VENTILATING FANS, WOOL AND COTTON DRYERS, Etc.

Catalogues free.

GEO. P. CLARK

Box L. Windsor Locks, Conn.

212° FAHR THE STEAM JACKET FEED WATER BOILER & PURIFIER. BOILS THE WATER. WM BARAGWANATH & SON, 46 W DIVISION ST CHICAGO. SEND FOR CATALOGUE.

WANTED—Manufacturer's Agent to handle new the best makes. One to take whole product preferred. Correspondence solicited. C. Lee Abell, Buffalo, N. Y.

DUST! DUST!

Gibbs Patent Dust Protector protects the nose and mouth from inhaling poisonous dust. Invaluable in every industry where dust is troublesome. Perfect protection with perfect ventilation. Inhalation of dust causes catarrh, consumption and many other serious disorders. Thousands in use. Price \$1.00, postpaid in U. S. and Canada; \$1.40 for foreign points. Gibbs Respirator Co., 31 La Salle St., Chicago.

FOOT POWER LATHES


For Electrical and Experimental Work. For Gunsmiths & Tool Makers. For General Machine Shop Work. High Grade Tools; elegant in design, superior in construction. The best foot power lathes made, and quality considered, the cheapest. Send for catalogue and prices. W. F. & JOHN BARNES CO., 1909 Ruby St., Rockford, Ill.

WRITE FOR McINTOSH & BOND CO. CATALOGUE. CHICAGO.

HAVE YOU READ

Experimental Science?

This new book, by Geo. M. Hopkins, is just what you need to give you a good general knowledge of Physical Science. No one having the spirit of the times can afford to be without the kind of scientific information contained in this book. It is not only instructive, but entertaining.



Over 700 pages; 680 fine cuts; substantially and beautifully bound. Price by mail, \$4.00.

Send for illustrated circular.

MUNN & CO., Publishers,

Office of the SCIENTIFIC AMERICAN,

361 BROADWAY, NEW YORK.

WORKING MODELS & LIGHT MACHINERY. INVENTIONS DEVELOPED. Send for Model Circular. Jones Bros. E Co., Cin'ti. O.

Advertisements.


Inside Page, each insertion - - 75 cents a line
Back Page, each insertion - - - \$1.00 a line
The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may be advertised at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at Publication Office as early as Thursday morning to appear in the following week's issue.

Victors
HIGHEST GRADE CATALOGUE FREE



OVERMAN WHEEL CO.
BOSTON, WASHINGTON, DENVER, SAN FRANCISCO.
A. G. SPALDING & BROS., Special Agents,
CHICAGO, NEW YORK, PHILADELPHIA.

"Rogers' Drive Screw."
Patented May 10, July 19, 1887;
July 10, 1888;
July 19, 1892.



It will turn like a screw into wood when driven with a hammer, and will not break the fibers of the wood.

It is cheaper than a common screw, and, being cold forged, the entire surface has a metallic skin.

For applying steps to Electric Light Poles, it has no superior.

Send for samples to
AMERICAN SCREW COMPANY,
PROVIDENCE, R. I.

THE AMERICAN BELL TELEPHONE CO.
95 MILK ST., BOSTON, MASS.

This Company owns the Letters Patent granted to Alexander Graham Bell, March 7th, 1876, No. 174,465, and January 30th, 1877, No. 186,787.

The transmission of Speech by all known forms of Electric Speaking Telephones infringes the right secured to this Company by the above patents, and renders each individual user of telephones not furnished by it or its licensees responsible for such unlawful use, and all the consequences thereof, and liable to suit therefor.

STEREOTYPING; THE PLASTER AND Paper Processes.—Composition and preparation of the mould, the best alloys of metal and proper degree of heat, trimming and mending the plates, etc. A minute description of both processes, with numerous illustrations. A paper of great interest to every printer. By Thomas Bolas, F.C.S., F.I.C. SCIENTIFIC AMERICAN SUPPLEMENTS, 773 and 774. 10 cents each.

Envy is easy for a happy man to bear—even from his friends.

It always seems to be excited by the new *quick-winding* Waterbury watch. It winds in about five seconds.

Coin-silver and gold filled cases make it beautiful to look at. It has a jeweled movement, and is an accurate timekeeper.

It is still a low-priced watch.

Jewelers sell it in several styles. 10.

PATENTS!

MESSRS. MUNN & CO., in connection with the publication of the SCIENTIFIC AMERICAN, continue to examine improvements, and to act as Solicitors of Patents for Inventors.

In this line of business they have had forty years' experience, and now have unequalled facilities for the preparation of Patent Drawings, Specifications, and the prosecution of Applications for Patents in the United States, Canada, and Foreign Countries. Messrs. Munn & Co. also attend to the preparation of Caveats, Copyrights for Books, Labels, Reissues, Assignments, and Reports on Infringements of Patents. All business entrusted to them is done with special care and promptness, on very reasonable terms.

A pamphlet sent free of charge, on application, containing full information about Patents and how to procure them; directions concerning Labels, Copyrights, Designs, Patents, Appeals, Reissues, Infringements, Assignments, Rejected Cases. Hints on the sale of Patents, etc.

We also send, free of charge, a Synopsis of Foreign Patent Laws, showing the cost and method of securing Patents in all the principal countries of the world.

MUNN & CO., Solicitors of Patents.

361 Broadway, New York.
BRANCH OFFICES.—No. 622 and 624 F Street, Pacific Building near 7th Street, Washington, D. C.

ELECTRIC MINING APPARATUS, ELECTRIC MINE LOCOMOTIVES ELECTRIC VENTILATING FANS ELECTRIC HOISTS & ELEVATORS ELECTRIC COAL CUTTERS.

THOMSON-HOUSTON ELECTRIC COMPANY, MINING DEPARTMENT.
622 ATLANTIC AVENUE, BOSTON, MASS. 173-175 ADAMS STREET, CHICAGO, ILL.

KODAKS

\$6.00 to \$65.00.

The New Model folding Kodak has glass plate attachment, Barker shutter, sliding front, automatic register, and can be used as a hand or tripod camera.

EASTMAN KODAK CO.,

Send for Circulars. Rochester, N. Y.

VANDUZEN STEAM PUMP
THE BEST IN THE WORLD.
Pumps Any Kind of Liquid.
Always in Order, never Clogs nor freezes. Every Pump Guaranteed.
10 SIZES.
200 to 12000 Gallons per Hour.
Cost \$7 to \$75 each. Address
THE VANDUZEN & TIFT CO.,
102 to 108 E. Second St., Cincinnati, O.

SAWS Wanted 50,000 Sawyers and Lumbermen to send us their full address for a copy of Emerson's Book of SAWS, new 1892 edition. We are first to introduce NATURAL GAS for heating and tempering Saws with wonderful effect upon improving their quality and toughness, enabling us to reduce prices. Address EMERSON SMITH & CO. (Limited), Beaver Falls, Pa.

HEADQUARTERS for LOW PRICES
We have all our good cash customers from 25 to 75 per cent. on all large variety of useful articles besides
400 Kinds of SCALES which we manufacture. Send for Circulars and Prices. The following are among the Articles we sell: Bicycles, Watches, Organs, Pianos, Sates, Sewing Machines, Carriages, Wagons, Road Cars, Sleighs, Buggies, Harness, Portable Forges, Anvils, Vices, Feed Mills, Bone Mills, Cider Mills, Etc. CHICAGO SCALE CO., Chicago

PERFORATORS OF ALL METALS
For Cotton, Oil and Rice Mills, Sugar Houses, Distilleries, Phosphate and Fertilizer Works, Mining and Concentrating, Gas and Water Works, Elevators, Threshers, Separators, Corn Shellers, and all kinds of Grain Cleaning Machinery. Heavy steel and Iron Plates and Cylinders for Screening Ore, Coal, Stone. For Filters, Strainers, Ventilators, Oil, Gas and Vapor Stoves and all special purposes. Special sizes for Coffee Cleaning and Roasting Machinery. Perforated Tin and Brass.
The Harrington & King Perforating Co., Chicago, and 284 Pearl St., N.Y.

THE HUB FRICTION CLUTCH,
applied to Pulleys, Gears, Sprocket Wheels, Reversible Counter-shafts and Cut-off Couplings. The most simple, effective, durable and economical Clutch on the market. Made in sizes to transmit from 2 up to 1000 h. p., at slow or fast speed. Over 10,000 in use. Write for cuts, description, price list and discounts, to the makers,
The James Smith
Woolen Machinery Co.,
411-421 Race St., Phila., Pa.

MAGIC LANTERNS
And STEREOTYPICONS, all prices. Views illustrating every subject for PUBLIC EXHIBITIONS, etc. Also Lanterns for Home Amusements. 236 page Catalogue free. McALLISTER, Mfg. Optician, 49 Nassau St., N.Y.

HARTFORD STEAM BOILER
HARTFORD, CONN.
INSPECTION AND INSURANCE CO.



NICKEL AND ELECTRO-PLATING
Apparatus and Material.
THE
Hanson & Van Winkle Co.
Newark, N. J.
81 LIBERTY ST., N. Y.
23 S. CANAL STREET, CHICAGO.

GENERAL ELECTRIC COMPANY.
EDISON and THOMSON-HOUSTON SYSTEMS.
INCANDESCENT and ARC LIGHTING.
STREET RAILWAYS.
TRANSMISSION OF POWER.
MINING BY ELECTRICITY.
Send for our NEW Catalogue.
BRANCH OFFICES:
620 Atlantic Avenue.....Boston, Mass.
173 and 175 Adams Street.....Chicago, Ill.
264 West Fourth Street.....Cincinnati, O.
Gould Building.....Atlanta, Ga.
42 Broad Street.....New York.
509 Arch Street.....Philadelphia, Pa.
401-407 Sibley Street.....St. Paul, Minn.
Masonic Temple.....Denver, Colo.
15 First Street.....San Francisco, Cal.

THE SMITH PREMIER TYPEWRITER



Important Improvements.
All the Essential Features greatly perfected
The Most Durable in Alignment.
Easiest Running and Most Silent.
All type cleaned in 10 seconds without soiling the hands
The Smith Premier Typewriter Co., Syracuse, N. Y., U. S. A.
Send for Catalogue.

ALUMINUM. AN INTERESTING DESCRIPTION of the various methods of manufacturing this metal, chemical and electrolytic, with special reference to the Heroult method. With 6 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 753. Price 10 cents. To be had at this office and from all newsdealers.

STOW FLEXIBLE SHAFT.
INVENTED AND MANUFACTURED BY THE
STOW MFG. CO.
440 STATE ST.
BINGHAMTON, N. Y.



SMOKELESS GUNPOWDER.—AN INTERESTING article by Hudson Maxim on the manufacture and use of smokeless gunpowder, giving a sketch of its history and the methods of producing it. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 751. Price 10 cents. To be had at this office and from all newsdealers.

USE GRINDSTONES?
If so, we can supply you. All sizes mounted and unmounted, always kept in stock. Remember, we make a specialty of selecting stones for all special purposes. Ask for catalogue.
The CLEVELAND STONE CO.
2d Floor, Wilshire, Cleveland, O.

A MODERN BATH.
The Latest and Best.
Quick self-heating or Toilet Cabinet in place of Heater. No bath room required. Ornamental, inexpensive, complete, practical. Desirable for city or town.
Send 2 ct. stamp for cutal.
The Mosely Folding Bath Tub Co.,
186 So. Canal St., Chicago.



Motor of 19th Century
Can be used Any Place, to do Any Work, and by Any One. No Boiler! No Fire! No Steam! No Ashes! No Gauges! No Engines! A perfectly safe Motor for all places and purposes. Cost of operation about one cent an hour to each indicated horse power. For circulars, etc., address
Economy, Reliability, Simplicity, Safety.
P. O. Box 148, Sterling, Ill.




TRADES UNIONS. THE TENDENCY of—By Herbert Spencer. An able paper, pointing out the great difficulties of dealing with complex social questions. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 801. Price 10 cents. To be had at this office and from all newsdealers.

THE ARMSTRONG MACHINES,
For Cutting Off and Threading Pipe.
For Hand or Power.
No. 1 cuts off and threads 1 to 3 inch.
No. 2 cuts off and threads 1 to 4 inch.
No. 3 cuts off and threads 1 to 6 inch.
Our aim is to make these machines as good as our Stocks and Dies, which are universally acknowledged to be THE BEST. Send for catalogue.
THE ARMSTRONG MFG. CO., Bridgeport, Ct.



THE GRAVES ELEVATORS.

THE STANDARD
H.W. JOHNS ASBESTOS BOILER COVERINGS
H.W. JOHNS MFG. CO.
87 MAIDEN LANE, NEW YORK.
PATENTED
CHICAGO, PHILADELPHIA, LONDON.



COMPTOMETER. Figures all Examples. Key operated. Rapid. Accurate. Relieves mental strain.
Send for Circular. F. & T. MFG. Co., 52-56 Illinois St. Chicago.

THE SCIENTIFIC AMERICAN

ESTABLISHED 1846.

The Most Popular Scientific Paper in the World
Only \$3.00 a Year, Including Postage.
Weekly—52 Numbers a Year.

This widely circulated and splendidly illustrated paper is published weekly. Every number contains sixteen pages of useful information and a large number of original engravings of new inventions and discoveries, representing Engineering Works, Steam Machinery, New Inventions, Novelties in Mechanics, Manufactures, Chemistry, Electricity, Telegraphy, Photography, Architecture, Agriculture, Horticulture, Natural History, etc. Complete list of patents each week.

Terms of Subscription.—One copy of the SCIENTIFIC AMERICAN will be sent for one year—52 numbers—postage prepaid, to any subscriber in the United States, Canada, or Mexico, on receipt of three dollars by the publishers; six months, \$1.50; three months, \$1.00.

Clubs.—Special rates for several names, and to Post Masters. Write for particulars.

The safest way to remit is by Postal Order, Draft, or Express Money Order. Money carefully placed inside of envelopes, securely sealed, and correctly addressed, seldom goes astray, but is at the sender's risk. Address all letters and make all orders, drafts, etc., payable to
MUNN & CO., 361 Broadway, New York.

THE SCIENTIFIC AMERICAN SUPPLEMENT

This is a separate and distinct publication from THE SCIENTIFIC AMERICAN, but is uniform therewith in size, every number containing sixteen large pages full of engravings, many of which are taken from foreign papers and accompanied with translated descriptions. THE SCIENTIFIC AMERICAN SUPPLEMENT is published weekly, and includes a very wide range of contents. It presents the most recent papers by eminent writers in all the principal departments of Science and the Useful Arts, embracing Biology, Geology, Mineralogy, Natural History, Geography, Archaeology, Astronomy, Chemistry, Electricity, Light, Heat, Mechanical Engineering, Steam and Railway Engineering, Mining, Ship Building, Marine Engineering, Photography, Technology, Manufacturing Industries, Sanitary Engineering, Agriculture, Horticulture, Domestic Economy, Biography, Medicine, etc. A vast amount of fresh and valuable information obtainable in no other publication.

The most important Engineering Works, Mechanisms, and Manufactures at home and abroad are illustrated and described in the SUPPLEMENT.

Price for the SUPPLEMENT for the United States and Canada, \$5.00 a year; or one copy of the SCIENTIFIC AMERICAN and one copy of the SUPPLEMENT, both mailed for one year for \$7.00. Single copies, 10 cents. Address and remit by postal order, express money order, or check,
MUNN & CO., 361 Broadway, New York.

Building Edition.

THE SCIENTIFIC AMERICAN ARCHITECTS' AND BUILDERS' EDITION is issued monthly. \$2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages; forming a large and splendid Magazine of Architecture, richly adorned with elegant plates in colors, and with other fine engravings; illustrating the most interesting examples of modern architectural construction and allied subjects.

A special feature is the presentation in each number of a variety of the latest and best plans for private residences, city and country, including those of very moderate cost as well as the more expensive. Drawings in perspective and in color are given, together with full Plans, Specifications, Sheets of Details, Estimates, etc.

The elegance and cheapness of this magnificent work have won for it the Largest Circulation of any Architectural publication in the world. Sold by all newsdealers. \$2.50 a year. Remit to

MUNN & CO., Publishers,
361 Broadway, New York.

COPPER TUBES.
SHEET BRASS BRASS WIRE
175 177 LAKE ST. CHICAGO

DEFIANCE MACHINE WORKS.
DEFIANCE, OHIO, U.S.A.
BUILDERS OF
HUB, SPOKE,
WHEEL, BENDING,
WAGON, CARRIAGE
AND HOOP
MACHINERY.
PATENT SPOKE DRIVER. SEND FOR CATALOGUE.



PRINTING INKS

THE SCIENTIFIC AMERICAN is printed with CHAS. ENEU JOHNSON & CO.'S INK, Tenth and Lombard Sts., Philadelphia, and 47 Rose St., opp. Duane, New York